




JEE (MAIN+ADVANCED)

Inorganic Chemistry

ENTHUSIAST COURSE



STUDY MATERIAL

p Block Element

English Medium

Copyright Statement

All rights including trademark and copyrights and rights of translation etc. reserved and vested exclusively with ALLEN Career Institute Private Limited. (ALLEN)

No part of this work may be copied, reproduced, adapted, abridged or translated, transcribed, transmitted, stored or distributed in any form retrieval system, computer system, photographic or other system or transmitted in any form or by any means whether electronic, magnetic, chemical or manual, mechanical, digital, optical, photocopying, recording or otherwise, or stored in any retrieval system of any nature without the written permission of the Allen Career Institute Private Limited. Any breach will entail legal action and prosecution without further notice.

This work is sold/distributed by Allen Career Institute Private Limited subject to the condition and undertaking given by the student that all proprietary rights (under the Trademark Act, 1999 and Copyright Act, 1957) of the work shall be exclusively belong to ALLEN Career Institute Private Limited. Neither the Study Materials and/or Test Series and/or the contents nor any part thereof i.e. work shall be reproduced, modify, re-publish, sub-license, upload on website, broadcast, post, transmit, disseminate, distribute, sell in market, stored in a retrieval system or transmitted in any form or by any means for reproducing or making multiple copies of it.

Any person who does any unauthorised act in relation to this work may be liable to criminal prosecution and civil claims for damages. Any violation or infringement of the propriety rights of Allen shall be punishable under Section- 29 & 52 of the Trademark Act, 1999 and under Section- 51, 58 & 63 of the Copyright Act, 1957 and any other Act applicable in India. All disputes are subjected to the exclusive jurisdiction of courts, tribunals and forums at Kota, Rajasthan only.

Note:- This publication is meant for educational and learning purposes. All reasonable care and diligence have been taken while editing and printing this publication. ALLEN Career Institute Private Limited shall not hold any responsibility for any error that may have inadvertently crept in. ALLEN Career Institute Private Limited is not responsible for the consequences of any action taken on the basis of this publication.

p-BLOCK

GROUP 13 ELEMENTS : THE BORON FAMILY :

Boron is a typical non-metal, aluminium is a metal but shows many chemical similarities to boron, and gallium, indium and thallium are almost exclusively metallic in character.

OCCURANCE

Boron : Boron is a fairly rare element, mainly occurs as orthoboric acid, (H_3BO_3) , borax, $\text{Na}_2\text{B}_4\text{O}_7 \cdot 10\text{H}_2\text{O}$, and kernite, $\text{Na}_2\text{B}_4\text{O}_7 \cdot 4\text{H}_2\text{O}$. There are two isotopic forms of boron ^{10}B (19%) and ^{11}B (81%).

ALUMINIUM :

Aluminium is the most abundant metal and the third most abundant element in the earth's crust (8.3% by mass) after oxygen (45.5%) and Si (27.7%). Bauxite, $\text{Al}_2\text{O}_3 \cdot 2\text{H}_2\text{O}$ and cryolite, Na_3AlF_6 are the important minerals of aluminium.

ELECTRONIC CONFIGURATION :

The outer electronic configuration of these elements is ns^2np^1 . A close look at the electronic configuration suggests that while boron and aluminium have noble gas core, gallium and indium have noble gas plus 10 d -electrons, and thallium has noble gas plus 14 f -electrons plus 10 d -electron cores. Thus, the electronic structures of these elements are more complex than for the first two groups of elements discussed in unit 10. This difference in electronic structures affects the other properties and consequently the chemistry of all the elements of this group.

ATOMIC RADII :

On moving down the group, for each successive member one extra shell of electrons is added and, therefore, atomic radius is expected to increase. However, a deviation can be seen.

Atomic radii order

$\text{B} < \text{Ga} < \text{Al} < \text{In} < \text{Tl}$

Ionic Radii order (+3 OS)

$\text{B} < \text{Al} < \text{Ga} < \text{In} < \text{Tl}$

Atomic radius of Ga is less than that of Al. This can be understood from the variation in the inner core of the electronic configuration. The presence of additional 10 d -electrons offer only poor screening effect for the outer electrons from the increased nuclear charge in gallium. Consequently, the atomic radius of gallium (135 pm) is less than that of aluminium (143 pm).

Ionization Enthalpy

The ionisation enthalpy values as expected from the general trends do not decrease smoothly down the group.

Ionization Enthalpies order

$\text{B} > \text{Tl} > \text{Ga} > \text{Al} > \text{In}$

The decrease from B to Al is associated with increase in size. The observed discontinuity in the ionisation enthalpy values between Al and Ga, and between In and Tl are due to inability of d - and f -electrons, which have low screening effect, to compensate the increase in nuclear charge. The order of ionisation enthalpies, as expected, is $\Delta_i\text{H}_1 < \Delta_i\text{H}_2 < \Delta_i\text{H}_3$. The sum of the first three ionisation enthalpies for each of the elements is very high. Effect of this will be apparent during study their chemical properties.

Electronegativity

Down the group, electronegativity first decreases from B to Al and then increases marginally. This is because of the discrepancies in atomic size of the elements.

Physical Properties

- (i) Boron is non-metallic in nature. It is extremely hard and black coloured solid. It exists in many allotropic forms. Due to very strong crystalline lattice, boron has unusually high melting point.
- (ii) Rest of the members are soft metals with low melting point and high electrical conductivity.
- (iii) It is worth while to note that gallium with unusually low melting point (303K), could exist in liquid state during summer. Its high boiling point (2676 K) makes it a useful material for measuring high temperatures.
- (iv) Density of the elements increases down the group from boron to thallium.

Melting and Boiling points order

M.P. $B > Al > Tl > In > Ga$


B.P. $B > Al > Ga > In > Tl$

Electropositive Character

Due to high IE they are less electropositive on moving down the group metallic character increases due to decrease in IE [$\therefore$ B is nonmetals and other elements are metals.]

B	$<$	Al	$>$	Ga	$>$	In	$>$	Tl
Non metal		Metals						

Note : Boron exists in many allotropic forms. All the allotropes have basic building B_{12} icosahedral units made up of polyhedron having 20 faces and 12 corners. For example one is the simplest form α - rhombohedral boron.




But Al, In & Tl all have close packed metal structure.


Chemical Properties***Oxidation state and trends in chemical reactivity***

- (i) Due to small size of boron, the sum of its first three ionization enthalpies is very high. This prevents it to form +3 ions and forces it to form only covalent compounds. But as we move from B to Al, the sum of the first three ionisation enthalpies of Al considerably decreases, and is therefore able to form Al^{3+} ions. In fact, aluminium is a highly electropositive metal.

- (ii) However, down the group, due to poor shielding effect of intervening d and f orbitals, the increased effective nuclear charge holds ns electrons tightly (responsible for inert pair effect) and thereby, restricting their participation in bonding. As a result of this, only p-orbital electrons may be involved in bonding. In fact in Ga, In and Tl, both +1 and +3 oxidation states are observed. The relative stability of +1 oxidation state progressively increases for heavier elements: $\text{Al} < \text{Ga} < \text{In} < \text{Tl}$. In thallium +1 oxidation state is predominant whereas the +3 oxidation state is highly oxidising in character.
- (iii) The compounds in +1 oxidation state, as expected from energy considerations, are more ionic than those in +3 oxidation state.
- (iv) In trivalent state, the number of electrons around the central atom in a molecule of the compounds of these elements (e.g., boron in BF_3) will be only six. Such **electron deficient** molecules have tendency to accept a pair of electrons to achieve stable electronic configuration and thus, behave as Lewis acids. The tendency to behave as Lewis acid decreases with the increase in the size down the group. BCl_3 easily accepts a lone pair of electrons from ammonia to form $\text{BCl}_3 \cdot \text{NH}_3$.





AlCl_3 achieves stability by forming a dimer



- (v) In trivalent state most of the compounds being covalent are hydrolysed in water. For example, the trichlorides on hydrolysis in water form tetrahedral $[\text{M}(\text{OH})_4]^-$ species; the hybridisation state of element M is sp^3 . Aluminium chloride in acidified aqueous solution forms octahedral $[\text{Al}(\text{H}_2\text{O})_6]^{3+}$ ion. In this complex ion, the 3d orbitals of Al are involved and the hybridisation state of Al is sp^3d^2 .

REACTIVITY TOWARDS AIR :

- (i) Boron is unreactive in crystalline form.
- (ii) Aluminium forms a very thin oxide layer on the surface which protects the metal from further attack.
- (iii) Amorphous boron and aluminium metal on heating in air form B_2O_3 and Al_2O_3 respectively. With dinitrogen at high temperature they form nitrides.



(E = element)

The nature of these oxides varies down the group. Boron trioxide is acidic and reacts with basic (metallic) oxides forming metal borates. Aluminium and gallium oxides are amphoteric and those of indium and thallium are basic in their properties.

Reaction with Air at Water

Al should react air to form a very thin oxide film (10^{-4} to 10^{-6} mm thick) on the surface and protects the metal from further attack




Ga and In are attacked neither by cold water nor hot water unless oxygen is present. Tl form an oxide on surface.


REACTIVITY TOWARDS ACIDS AND ALKALIES :

Boron does not react with acids and alkalies even at moderate temperature; but aluminium dissolves in mineral acids and aqueous alkalies and thus shows amphoteric character.

Aluminium dissolves in dilute HCl and liberates dihydrogen.




However, concentrated nitric acid renders aluminium passive by forming a protective oxide layer on the surface. Aluminium also reacts with aqueous alkali and liberates dihydrogen.



Sodium tetrahydroxoaluminate(III)

or



Ga, In, Tl dissolve in dilute acids liberating H_2 . Ga is amphoteric like Al and it dissolves in aq. NaOH liberating H_2 and forming gallates.


Reactivity towards halogens :

These elements react with halogens to form trihalides (except TlI_3).

**IMPORTANT TRENDS AND ANOMALOUS PROPERTIES OF BORON**

Certain important trends can be observed in the chemical behaviour of group 13 elements. The tri-chlorides, bromides and iodides of all these elements being covalent in nature are hydrolysed in water. Species like tetrahedral $[\text{M}(\text{OH})_4]^{-}$ and octahedral $[\text{M}(\text{H}_2\text{O})_6]^{3+}$, except in boron, exist in aqueous medium.



The monomeric trihalides, being electron deficient, are strong Lewis acids. Boron trifluoride easily reacts with Lewis bases such as NH_3 to complete octet around boron.




It is due to the absence of d orbitals that the maximum covalence of B is 4. Since the d orbitals are available with Al and other elements, the maximum covalence can be expected beyond 4. Most of the other metal halides (e.g., AlCl_3) are dimerised through halogen bridging (e.g., Al_2Cl_6). The metal species completes its octet by accepting electrons from halogen in these halogen bridged molecules.

Preparation of Boron :


- (i) Preparation of
- B_2O_3
- from Borax or Colemanite





- (ii) Reduction of
- B_2O_3

**□ Chemical Properties :**

- (i) Burning in air :
- $4B + 3O_2 \longrightarrow 2B_2O_3$






- (ii) Reaction with water




(red hot)

- (iii)
- $B + HCl \longrightarrow$
- no reaction



[$Al + HNO_3(80\%) \longrightarrow Al_2O_3$ (passive layer) and does not react further.]

- (iv)
- $2B + 2NaOH + 2H_2O \xrightarrow{\Delta} 2NaBO_2 + 3H_2$





- (v)
- $2B + N_2 \longrightarrow 2BN$
- $(2Al + N_2 \longrightarrow 2AlN)$




- (vi)
- $3Mg + 2B \longrightarrow Mg_3B_2$

SOME IMPORTANT COMPOUNDS OF BORON

Some useful compounds of boron are borax, orthoboric acid and diborane. We will briefly study their chemistry.

Preparation of Borax :**Borax****Properties :**

- (i) It is a white crystalline solid of formula $\text{Na}_2\text{B}_4\text{O}_7 \cdot 10\text{H}_2\text{O}$. In fact it contains the tetranuclear units $[\text{B}_4\text{O}_5(\text{OH})_4]^{2-}$ and correct formula; therefore, is $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 8\text{H}_2\text{O}$.
- (ii) Borax dissolves in water to give an alkaline solution.
 $\text{Na}_2\text{B}_4\text{O}_7 + 7\text{H}_2\text{O} \rightarrow 2\text{NaOH} + 4\text{H}_3\text{BO}_3$
Orthoboric acid
- (iii) On heating, borax first loses water molecules and swells up. On further heating it turns into a transparent liquid, which solidifies into glass like material known as borax bead.




The metaborates of many transition metals have characteristic colours and, therefore, borax bead test can be used to identify them in the laboratory. For example, when borax is heated in a Bunsen burner flame with CoO on a loop of platinum wire, a blue coloured $\text{Co}(\text{BO}_2)_2$ bead is formed.

Orthoboric acid :**Preparation :**

- (i) It can be prepared by acidifying an aqueous solution of borax.
 $\text{Na}_2\text{B}_4\text{O}_7 + 2\text{HCl} + 5\text{H}_2\text{O} \rightarrow 2\text{NaCl} + 4\text{B}(\text{OH})_3$
- (ii) It is also formed by the hydrolysis (reaction with water or dilute acid) of most boron compounds (halides, hydrides, etc.)

Property :



- (i) Orthoboric acid, H_3BO_3 is a white crystalline solid, with soapy touch.
- (ii) It is sparingly soluble in water but highly soluble in hot water.
- (iii) H_3BO_3 is soluble in water and behaves as weak monobasic acid. It does not donate protons like most the acids, but rather it accepts OH^- . It therefore is Lewis acid ($\text{B}(\text{OH})_3$)




or



Since B(OH)_3 only partially reacts with water to form H_3O^+ and $[\text{B(OH)}_4]^-$ it behaves as a weak acid. Thus it cannot be titrated satisfactorily with NaOH as a sharp end point is not obtained. If certain polyhydroxy compounds such as glycerol, mannitol or sugar are added to the titration mixture then B(OH)_3 behaves as a strong monobasic acid. and hence can now be titrated with NaOH and end point is diluted using phenolphthalein as indicator.





The added compound must be a cis diol to enhance the acidic properties in this way the cis-diol forms very stable complexes with $[\text{B(OH)}_4]^-$ formed in forward direction above, thus effectively removing it from solution. Hence reaction proceeds in forward direction (Le-Chatelier principle.)




On heating, orthoboric acid above 370K forms metaboric acid, HBO_2 which on further heating yields boric oxide, B_2O_3 .

□ **Heating of boric acid :**



STRUCTURE

It has a layer structure in which planar BO_3 units are joined by hydrogen bonds as shown in figure.



*Structure of boric acid; the dotted lines represent hydrogen bonds***Uses of boric acid :**


- (i) Boric acid is used in manufacturing of optical glasses
- (ii) With borax, it is used in the preparation of a buffer solution.

□ Diborane, B₂H₆


The simplest boron hydride known, is diborane.

Preparation :





- (i) It is prepared by treating boron trifluoride with LiAlH₄ in diethyl ether.




- (ii) **Laboratory method :** For the preparation of diborane involves the oxidation of sodium borohydride with iodine.



- (iii) **Industrial scale :** By the reaction of BF₃ with sodium hydride.



**Other reaction of preparation of B₂H₆ :****Properties :**

- (i) Diborane is a colourless, highly toxic gas with a b.p. of 180 K.
- (ii) Diborane catches fire spontaneously upon exposure to air.
- (iii) It burns in oxygen releasing an enormous amount of energy.





Most of the higher boranes are also spontaneously flammable in air.



- (iv) Boranes are readily hydrolysed by water to give boric acid.




- (v) Diborane undergoes cleavage reactions with Lewis bases(L) to give borane adducts, BH₃.L



Reaction of ammonia with diborane gives initially B₂H₆.2NH₃ which is formulated as [BH₂(NH₃)₂]⁺ [BH₄]⁻ ; further heating gives borazine, B₃N₃H₆ known as “inorganic benzene” in view of its ring structure with alternate BH and NH groups.




- (vi) Reaction with MeOH



Structure & bonding in diborane :

The structure of diborane is shown in figure. The four terminal hydrogen atoms and the two boron atoms lie in one plane. Above and below this plane, there are two bridging hydrogen atoms. The four terminal B–H bonds are regular two centre-two electron bonds while the two bridge (B–H–B) bonds are different and can be described in terms of three centre-two electron bonds shown in figure.



The structure of diborane, B_2H_6




Figure: Bonding in diborane.




Each B atom uses sp^3 hybrid orbitals for bonding. Out of the four sp^3 hybrid orbital on each B atom, one is without an electron shown in broken lines. The terminal B–H bonds are normal 2-centre-2-electron bonds but the two bridge bonds are 3-centre-2-electron bonds. The 3-centre-2-electron bridge bonds are also referred to as banana bonds.

Note: Metal hydrido borates : Boron also forms a series of hydridoborates; the most important one is the tetrahedral $[BH_4]^-$ ion. Tetrahydridoborates of several metals are known. Lithium and sodium tetrahydridoborates, also known as borohydrides, are prepared by the reaction of metal hydrides with B_2H_6 in diethyl ether.



Both $LiBH_4$ and $NaBH_4$ are used as reducing agents in organic synthesis. They are useful starting materials for preparing other metal borohydrides.

❑ **Al_2O_3 preparation :**





Uses: (i) In making refractory bricks

(ii) as an abrasive

(iii) To make high alumina cement

❑ **$AlCl_3$ preparation :**






Solid anh. AlCl_3

Properties :

- (i) Its anhydrous form is deliquescent and fumes in air.
- (ii) It sublimes at 180°C .
- (iii) It is covalent and exists in the form of dimer even if in non polar solvents e.g. alcohol, ether, benzene, where it is soluble in fair extent.



- Uses:** (i) Friedel-Craft reaction
(ii) Dyeing, drug & perfumes etc.

□ **Alums :** $\text{M}_2\text{SO}_4 \cdot \text{M}'_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$

Properties: Swelling characteristics

where $\text{M} = \text{Na}^+, \text{K}^+, \text{Rb}^+, \text{Cs}^+, \text{Ag}^+, \text{Tl}^+, \text{NH}_4^+$ (except Li^+)

$\text{M}' = \text{Al}^{+3}, \text{Cr}^{+3}, \text{Fe}^{+3}, \text{Mn}^{+3}, \text{Co}^{+3}$

$\text{K}_2\text{SO}_4 \cdot \text{Al}_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$ Potash alum

$(\text{NH}_4)_2\text{SO}_4 \cdot \text{Al}_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$ Ammonium alum

$\text{K}_2\text{SO}_4 \cdot \text{Cr}_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$ Chrome alum

$(\text{NH}_4)_2\text{SO}_4 \cdot \text{Fe}_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$ Ferric alum

Preparation: $\text{Al}_2\text{O}_3 + 3\text{H}_2\text{SO}_4 \longrightarrow \text{Al}_2(\text{SO}_4)_3 + 3\text{H}_2\text{O}$

$\text{Al}_2(\text{SO}_4)_3 + \text{K}_2\text{SO}_4 + \text{aq. sol}^n \longrightarrow \text{crystallise}$

- Uses :**
- (i) Act as coagulant
 - (ii) Purification of water
 - (iii) Tanning of leather
 - (iv) Mordant in dying
 - (v) Antiseptic

USES OF BORON AND ALUMINIUM AND THEIR COMPOUNDS

Boron :

- (i) Boron being extremely hard refractory solid of high melting point, low density and very low electrical conductivity, finds many applications.
- (ii) Boron fibres are used in making bullet-proof vest and light composite material for aircraft.
- (iii) The boron-10 (^{10}B) isotope has high ability to absorb neutrons and, therefore, metal borides are used in nuclear industry as protective shields and control rods.
- (iv) The main industrial application of borax and boric acid is in the manufacture of heat resistant glasses(e.g., Pyrex), glass-wool and fibreglass.
- (v) Borax is also used as a flux for soldering metals, for heat, scratch and stain resistant glazed coating to earthenwares and as constituent of medicinal soaps.
- (vi) An aqueous solution of orthoboric acid is generally used as a mild antiseptic.

Aluminium :

- (i) Aluminium is a bright silvery-white metal, with high tensile strength.
- (ii) It has a high electrical and thermal conductivity.
- (iii) On a weight-to-weight basis, the electrical conductivity of aluminium is twice that of copper.
- (iv) Aluminium is used extensively in industry and every day life.
- (v) It forms alloys with Cu, Mn, Mg, Si and Zn.
- (vi) Aluminium and its alloys can be given shapes of pipe, tubes, rods, wires, plates or foils and, therefore, find uses in packing, utensil making, construction, aeroplane and transportation industry.
- (vii) The use of aluminium and its compounds for domestic purposes is now reduced considerably because of their toxic nature.

GROUP 14 ELEMENTS :**The carbon family**

Carbon (C), silicon (Si), germanium (Ge), tin (Sn) and lead (Pb) are the members of group 14.

❑ Occurrence of element

- (i) **Carbon** : Carbon is the seventeenth most abundant element by mass in the earth's crust. Naturally occurring carbon contains two stable isotopes: ^{12}C and ^{13}C . In addition to these, third isotope, ^{14}C is also present. It is a radioactive isotope with half-life 5770 years and used for radiocarbon dating.
- (ii) **Silicon** : Silicon is the second (27.7 % by mass) most abundant element on the earth's crust and is present in nature in the form of silica and silicates. Silicon is a very important component of ceramics, glass and cement.
- (iii) **Germanium** : Germanium exists only in traces.
- (iv) **Tin** : Tin occurs mainly as cassiterite, SnO_2
- (v) **Lead** : Lead as galena, PbS .

Note : Ultrapure form of germanium and silicon are used to make transistors and semiconductor devices.

❑ Electronic Configuration

The valence shell electronic configuration of these elements is ns^2np^2 . The inner core of the electronic configuration of elements in this group also differs.

❑ Covalent Radius

There is a considerable increase in covalent radius from C to Si, thereafter from Si to Pb a small increase in radius is observed. This is due to the presence of completely filled d and f orbitals in heavier members.

Covalent radii : $\text{C} < \text{Si} < \text{Ge} < \text{Sn} < \text{Pb}$

❑ Ionization Enthalpy

The first ionization enthalpy of group 14 members is higher than the corresponding members of group 13. The influence of inner core electrons is visible here also. In general the ionisation enthalpy decreases down the group. Small decrease in $\Delta_i H$ from Si to Ge, Ge to Sn and slight increase in $\Delta_i H$ from Sn to Pb is the consequence of poor shielding effect of intervening d and f orbitals and increase in size of the atom.

$\text{C} > \text{Si} > \text{Ge} > \text{Pb} > \text{Sn}$ (IE_1 values)
--

❑ Melting and Boiling Points

M.P. : $C > Si > Ge > Pb > Sn$

B.P. : $Si > Ge > Sn > Pb$

❑ Electronegativity

Due to small size, the elements of this group are slightly more electronegative than group 13 elements. The electronegativity values for elements from Si to Pb are almost the same.

❑ Physical Properties

All group 14 members are solids. Carbon and silicon are non-metals, germanium is a metalloid, whereas tin and lead are soft metals with low melting points. Melting points and boiling points of group 14 elements are much higher than those of corresponding elements of group 13.

❑ Chemical Properties***Oxidation states and trends in chemical reactivity***


- (i) The group 14 elements have four electrons in outermost shell.
- (ii) The common oxidation states exhibited by these elements are +4 and +2. Carbon also exhibits negative oxidation states. Since the sum of the first four ionization enthalpies is very high, compounds in +4 oxidation state are generally covalent in nature.
- (iii) In heavier members the tendency to show +2 oxidation state increases in the sequence $Ge < Sn < Pb$. It is due to the inability of ns^2 electrons of valence shell to participate in bonding. The relative stabilities of these two oxidation states vary down the group.
- (iv) Carbon and silicon mostly show +4 oxidation state.
- (v) Germanium forms stable compounds in +4 state and only few compounds in +2 state.
- (vi) Tin forms compounds in both oxidation states (Sn in +2 state is a reducing agent).
- (vii) Lead compounds in +2 state are stable and in +4 state are strong oxidising agents.
- (viii) In tetravalent state the number of electrons around the central atom in a molecule (e.g., carbon in CCl_4) is eight. Being *electron precise* molecules, they are normally not expected to act as electron acceptor or electron donor species. Although carbon cannot exceed its covalence more than 4, other elements of the group can do so. It is because of the presence of d orbital in them. Due to this, their halides undergo hydrolysis and have tendency to form complexes by accepting electron pairs from donor species. For example, the species like, SiF_6^{2-} , $[GeCl_6]^{2-}$, $[Sn(OH)_6]^{2-}$ exist where the hybridisation of the central atom is sp^3d^2 .

❑ Reactivity towards oxygen

All members when heated in oxygen form oxides. There are mainly two types of oxides, i.e., monoxide and dioxide of formula MO and MO_2 respectively. SiO only exists at high temperature. Oxides in higher oxidation states of elements are generally more acidic than those in lower oxidation states. The dioxides — CO_2 , SiO_2 and GeO_2 are acidic, whereas SnO_2 and PbO_2 are amphoteric in nature. Among monoxides, CO is neutral, GeO is distinctly acidic whereas SnO and PbO are amphoteric.

□ Reactivity towards water


Carbon, silicon and germanium are not affected by water. Tin decomposes steam to form dioxide and dihydrogen gas.



Lead is unaffected by water, probably because of a protective oxide film formation.

□ Reactivity towards halogen

- These elements can form halides of formula MX_2 and MX_4 (where $\text{X} = \text{F}, \text{Cl}, \text{Br}, \text{I}$). Except carbon, all other members react directly with halogen under suitable condition to make halides.
- Most of the MX_4 are covalent in nature. The central metal atom in these halides undergoes sp^3 hybridisation and the molecule is tetrahedral in shape. Exceptions are SnF_4 and PbF_4 , which are ionic in nature.
- PbI_4 does not exist because Pb—I bond initially formed during the reaction does not release enough energy to unpair $6s^2$ electrons and excite one of them to higher orbital to have four unpaired electrons around lead atom.
- Heavier members Ge to Pb are able to make halides of formula MX_2 .
- Stability of dihalides increases down the group. Considering the thermal and chemical stability, GeX_4 is more stable than GeX_2 , whereas PbX_2 is more than PbX_4 .
- Except CCl_4 , other tetrachlorides are easily hydrolysed by water because the central atom can accommodate the lone pair of electrons from oxygen atom of water molecule in d orbital. Hydrolysis can be understood by taking the example of SiCl_4 . It undergoes hydrolysis by initially accepting lone pair of electrons from water molecule in d orbitals of Si, finally leading to the formation of Si(OH)_4 as shown below :



IMPORTANT TRENDS AND ANOMALOUS BEHAVIOUR OF CARBON

Like first member of other groups, carbon also differs from rest of the members of its group. It is due to its smaller size, higher electronegativity, higher ionisation enthalpy unavailability of d orbitals.

In carbon, only s and p orbitals are available for bonding and, therefore, it can accommodate only four pairs of electrons around it. This would limit the maximum covalence to four whereas other members can expand their covalence due to the presence of d orbitals.

Carbon also has unique ability to form $p_\pi-p_\pi$ multiple bonds with itself and with other atoms of small size and high electronegativity. Few examples of multiple bonding are: $\text{C}=\text{C}$, $\text{C}\equiv\text{C}$, $\text{C}=\text{O}$, $\text{C}=\text{S}$ and $\text{C}\equiv\text{N}$. Heavier elements do not form $p_\pi-p_\pi$ bonds because their atomic orbitals are too large and diffuse to have effective overlapping.

Catenation Property

Carbon atoms have the tendency to link with one another through covalent bonds to form chains and rings. This property is called **catenation**. This is because C—C bonds are very strong. Down the group the size increases and electronegativity decreases, and, thereby, tendency to show catenation decreases. This can be clearly seen from bond enthalpies values. The order of catenation is $C \gg Si > Ge \approx Sn$. Lead does not show catenation.

Bond	Bond enthalpy/kJ mol ⁻¹
C—C	348
Si—Si	297
Ge—Ge	260
Sn—Sn	240

Due to property of catenation and $p_\pi-p_\pi$ bond formation, carbon is able to show allotropic forms.

ALLOTROPES OF CARBON

Carbon exhibits many allotropic forms; both crystalline as well as amorphous. Diamond and graphite are two well-known crystalline forms of carbon. In 1985, third form of carbon known as **fullerenes** was discovered by H.W. Kroto, E. Smalley and R.F. Curl. For this discovery they were awarded the Nobel Prize in 1996.




SOME IMPORTANT COMPOUNDS OF CARBON AND SILICON**□ Types of Carbide**

(i) Ionic and salt like:



Classification on basis of
no. of carbon atoms
present in hydrocarbon
found on their hydrolysis

- (a) C₁ unit
- (b) C₂ unit
- (c) C₃ unit

C₁ unit :



C₂ unit :



C₃ unit :





(ii) Covalent carbide : SiC & B₄C

(iii) Interstitial carbide :

(Transition element or inner transitional elements forms this kind of carbide)

Interstitial carbide formation doesn't affect the metallic lusture and electrical conductivity.

($\therefore$ no chemical bond is present, no change in property)

SiC (Carborundum)**□ Preparation**

Note :


- (i) SiC has diamond like or wurtzite structure
- (ii) SiC is often dark purple, black or dark green due to traces of Fe and other impurities but pure sample are pale yellow to colourless.

Properties


- (i) It is very hard and is used in cutting tools and abrasive powder (polishing material)
- (ii) It is very much inert
- (iii) It is not being affected by any acid except H_3PO_4

□ Carbon Monoxide**Preparation :**


- (i) Direct oxidation of C in limited supply of oxygen or air yields carbon monoxide.



- (ii) On small scale pure CO is prepared by dehydration of formic acid with concentrated H_2SO_4 at 373 K



- (iii) On commercial scale it is prepared by the passage of steam over hot coke. The mixture of CO and H_2 thus produced is known as **water gas** or **synthesis gas**.








When air is used instead of steam, a mixture of CO and N_2 is produced, which is called **producer gas**.





Water gas and producer gas are very important industrial fuels. Carbon monoxide in water gas or producer gas can undergo further combustion forming carbon dioxide with the liberation of heat.

- (iv) **By heating potassium ferrocyanide with conc. H_2SO_4 :** When potassium ferrocyanide in powdered state is heated with concentrated H_2SO_4 , CO is evolved. Dilute H_2SO_4 should never be used because it shall evolve highly poisonous gas HCN.




Properties :

- (i) Carbon monoxide is a colourless, odourless and almost water insoluble gas.
- (ii) It is a powerful reducing agent and reduces almost all metal oxides other than those of the alkali and alkaline earth metals, aluminium and a few transition metals. This property of CO is used in the extraction of many metals from their oxides ores.




**DETECTION**

(a) burns with blue flame

(b) CO is passed through PdCl_2 solution giving rise to black ppt.



Black metallic
deposition

ESTIMATION**ABSORBERS**

❑ **Bonding in CO mole**

In CO molecule, there are one sigma and two π bonds between carbon and oxygen. Because of the presence of a lone pair on carbon, CO molecule acts as a donor and reacts with certain metals when heated to form **metal carbonyls**.



❑ **Poisonous nature of CO**

The highly poisonous nature of CO arises because of its ability to form a **complex with haemoglobin**, which is about 300 times more stable than the oxygen-haemoglobin complex. This prevents haemoglobin in the red blood corpuscles from carrying oxygen round the body and ultimately resulting in death.

❑ **Carbon Dioxide**

Preparation :

- (i) It is prepared by complete combustion of carbon and carbon containing fuels in excess of air.





- (ii) **Laboratory** by the action of dilute HCl on calcium carbonate.



- (iii) Commercial scale by heating limestone.

Properties :


- (i) It is a colourless and odourless gas.
- (ii) Its low solubility in water makes it of immense biochemical and geo-chemical importance.
- (iii) With water, it forms carbonic acid, H_2CO_3 which is a weak dibasic acid and dissociates in two steps:



$\text{H}_2\text{CO}_3/\text{HCO}_3^-$ buffer system helps to maintain pH of blood between 7.26 to 7.42. Being acidic in nature, it combines with alkalies to form metal carbonates.

Use of CO_2

Carbon dioxide, which is normally present to the extent of $\sim 0.03\%$ by volume in the atmosphere, is removed from it by the process known as **photosynthesis**. It is the process by which green plants convert atmospheric CO_2 into carbohydrates such as glucose. The overall chemical change can be expressed as:




By this process plants make food for themselves as well as for animals and human beings.

Harmful effect of CO_2

Unlike CO, it is not poisonous. But the increase in combustion of fossil fuels and decomposition of limestone for cement manufacture in recent years seem to increase the CO_2 content of the atmosphere. This may lead to increase in **green house effect** and thus, raise the temperature of the atmosphere which might have serious consequences.



- (i) Carbon dioxide can be obtained as a solid in the form of **dry ice** by allowing the liquified CO_2 to expand rapidly and dry ice is used as a refrigerant for ice-cream and frozen food.
- (ii) Gaseous CO_2 is extensively used to carbonate soft drinks. Being heavy and non-supporter of combustion it is used as fire extinguisher.
- (iii) A substantial amount of CO_2 is used to manufacture urea. In CO_2 molecule carbon atom undergoes sp hybridisation. Two sp hybridised orbitals of carbon atom overlap with two p orbitals of oxygen atoms to make two sigma bonds while other two electrons of carbon atom are involved in $p_\pi-p_\pi$ bonding with oxygen atom. This results in its linear shape [with both C–O bonds of equal length (115 pm)] with no dipole moment. The resonance structures are shown below:



Resonating structures of carbon dioxide

Note : Carbongene has 95% O_2 and 5% CO_2 and is used as an antidote for poisoning of CO.

❑ Teflon



❑ Purpose

Temperature with standing capacity upto 300°C (1st organic compound withstand this kind of high temperature)

SILICON (Si)


❑ Occurrence

Silicon is the second most abundant (27.2%) element after oxygen (45.5%) in the earth's crust. It does not occur free in nature but in the combined state, it occurs widely in form of silica and silicates. All mineral rocks, clays and soils are built of silicates of magnesium, aluminium, potassium or iron. Aluminium silicate is however the most common constituent of rocks and clays. Silica is found in the free state in sand, flint and quartz and in the combined state as silicates like

- (i) Feldspar – K₂O. Al₂O₃. 6SiO₂
- (ii) Kaolinite – Al₂O₃. 2SiO₂. 2H₂O
- (iii) Asbestos – CaO. 3MgO. 4SiO₂

Preparation

- (i) From silica (sand): Elemental silicon is obtained by the reduction of silica (SiO₂) with high purity coke in an electric furnace.



- (ii) From silicon tetrachloride (SiCl₄) or silicon chloroform (SiHCl₃) : Silicon of very high purity required for making semiconductors is obtained by reduction of highly purified silicon tetrachloride or silicon chloroform with dihydrogen followed by purification by zone refining.




❑ Physical Properties :

- (i) Elemental silicon is very hard having diamond like structure.
- (ii) It has shining luster with a melting point of 1793 K and boiling point of about 3550 K.
- (iii) Silicon exists in three isotopes, i.e. $^{28}_{14}\text{Si}$, $^{29}_{14}\text{Si}$ and $^{30}_{14}\text{Si}$ but $^{28}_{14}\text{Si}$ is the most common isotope.


❑ Chemical Properties :

Silicon is particularly unreactive at room temperature towards most of the elements except fluorine. Some important chemical reactions of silicon are discussed below.

- (i) **Action of air** : Silicon reacts with oxygen of air at 1173 K to form silicon dioxide and with nitrogen of air at 1673 K to form silicon nitride,.




Silicon dioxide




Silicon nitride

- (ii) **Action of steam** : It is slowly attacked by steam when heated to redness liberating dihydrogen gas.




- (iii) **Reaction with halogens**: It burns spontaneously in fluorine gas at room temperature to form silico tetrafluoride (SiF_4).



However, with other halogens, it combines at high temperatures forming tetrahalides.

- (iv) **Reaction with carbon** : Silicon combines with carbon at 2500°C forming silicon carbide (SiC) known as carborundum.



Carborundum is an extremely hard substance next only to diamond. It is mainly used as an abrasive and as a refractory material.

Uses :

- Silicon is added to steel as such or more usually in form of ferrosilicon (an alloy of Fe and Si) to make it acid-resistant.
- High purity silicon is used as semiconductors in electronic devices such as transistors.
- It is used in the preparation of alloys such as silicon-bronze, magnesium silicon bronze and ferrosilicon.


❑ Compounds of Silicon :

Silane :



Only these two are found

Higher molecules are not formed. $\therefore$ Si can't show catenation property




Silicones


It is an organosilicon polymer

TYPES OF SILICONES :

(i) Linear silicones



Linear Silicone



SILICA (SiO₂)


Occurrence :

Silica or silicon dioxide occurs in nature in the free state as sand, quartz and flint and in the combined state as silicates like, Feldspar : K₂O.Al₂O₃.6SiO₂, Kaolinite : Al₂O₃. 2SiO₂. 2H₂O etc.


Properties :

(i) Pure silica is colourless, but sand is usually coloured yellow or brown due to the presence of ferric oxide as an impurity.




(ii) Silicon dioxide is insoluble in water and all acids except hydrofluoric acid.



(iii) It also combines with metallic oxides at high temperature giving silicates e.g.




(iv) When silica is heated strongly with metallic salts, silicates are formed and the volatile oxides are driven off as vapours.



The first two examples quoted here are important in glass making.

□ Structures of Silica :

Silica has a three-dimensional network structure. In silica, silicon is sp³-hybridized and is thus linked to four oxygen atoms and each oxygen atom is linked to two silicon atoms forming a three-dimensional giant molecule as shown in figure. This three-dimensional network structure imparts stability to SiO₂ crystal and hence a large amount of energy is required to break the crystal resulting in high melting point.



Uses :

(i) Sand is used in large quantities to make mortar and cement.

(ii) Being transparent to ultraviolet light, large crystal of quartz are used for making lenses for optical instruments and for controlling the frequency of radio-transmitters.

(iii) Powdered quartz is used for making silica bricks.

(iv) Silica gel (SiO₂.xH₂O) is used as a desiccant (for absorbing moisture) and as an adsorbent in chromatography.

Quartz



Quartz is extensively used as a piezoelectric material; it has made possible to develop extremely accurate clocks, modern radio and television broadcasting and mobile radio communications. Silica gel is used as a drying agent and as a support for chromatographic materials and catalysts. Kieselghur, an amorphous form of silica is used in filtration plants.

Silicates


A large number of silicates minerals exist in nature. Some of the examples are feldspar, zeolites, mica and asbestos. Two important man-made silicates are glass and cement.

Zeolites



If aluminium atoms replace few silicon atoms in three-dimensional network of silicon dioxide, overall structure known as aluminosilicate, acquires a negative charge. Cations such as Na^+ , K^+ or Ca^{2+} balance the negative charge. Examples are feldspar and zeolites. Zeolites are widely used as a catalyst in petrochemical industries for cracking of hydrocarbons and isomerisation, e.g., ZSM-5 (A type of zeolite) used to convert alcohols directly into gasoline. Hydrated zeolites are used as ion exchangers in softening of "hard" water.

TIN & ITS COMPOUND

(iii) Reaction with acid.




Metastannic acid






or




KOH [In absence of air K_2SnO_2 forms and in contact with air it readily converts into K_2SnO_3]




Both are amphoteric in nature :







But conc. hot alkali behaves differently.






(Soluble only in hot conc. H_2SO_4)








SnCl_2 & SnCl_4 :






(2) A piece of Sn is always added to preserve a solution of SnCl_2 . Explain.



(4) Reducing Properties of SnCl_2 :




(5) Readily combines with $\text{I}_2 \Rightarrow \text{SnCl}_2\text{I}_2 \Rightarrow$ This reaction is used to estimate tin.

Formation of SnCl_4 :

* $\text{SnCl}_4 \cdot 5\text{H}_2\text{O}$ is known as butter of tin $\Rightarrow$ used as mordant.


$(\text{NH}_4)_2 \text{SnCl}_6$ is known as 'pink's salt' $\Rightarrow$ used in calico printing.

Mosaic gold : SnS_2 yellow crystalline substance :



Note : Mosaic gold used for filling purpose (in joining gold pieces)

* **Distinction of Sn^{+2} / Sn^{+4} :**

**COMPOUNDS OF LEAD**


Oxides of lead :

(i) PbO



(ii) Pb_3O_4 (Red)

(iii) Pb_2O_3 (reddish yellow) (Sesquioxide)

(iv) PbO_2 (dark brown)







Laboratory Prepⁿ. :



Preparation of Pb_2O_3 :





This reaction suggests that Pb_2O_3 contains PbO_2 .



(3) **PbO₂** : Insoluble in water :

HNO₃, But reacts with HCl and H₂SO₄(hot conc.) but does not react with HNO₃ and soluble in hot NaOH/KOH.






↓




Excess bleaching powder

is being removed by stirring with


HNO₃




PbO₂ : Powerful oxidising agent :




PbCl₄ : Exists as H₂[PbCl₆]



{ice cold conc. saturated with Cl₂}



TetraEthyl lead :



It is antiknocking agent.

NITROGEN FAMILY

GROUP-15 ELEMENTS (N, P, As, Sb, Bi)

- (i) As we go down the group, there is a shift from non-metallic to metallic through metalloidic character.
- (ii) Nitrogen and phosphorus are **non-metals**, arsenic and antimony **metalloids** and bismuth is a **typical metal**.

Occurrence :

Nitrogen : Molecular nitrogen comprises 78% by volume of the atmosphere. It is 33rd most abundant element in the earth's crust. In the earth's crust, it occurs as sodium nitrate, NaNO_3 (called Chile saltpetre) and potassium nitrate (Indian saltpetre). It is found in the form of proteins and nucleic acid in plants and animals.

Phosphorus :

- (i) It is eleventh most abundant element in earth's crust occurs in minerals of the apatite family, $\text{Ca}_5(\text{PO}_4)_3\text{CaX}_2$ ($\text{X} = \text{F}, \text{Cl}$ or OH) (e.g., fluorapatite $\text{Ca}_5(\text{PO}_4)_3\text{CaF}_2$) and also found as chlorapatite $\text{Ca}_5(\text{PO}_4)_3\text{CaCl}_2$.
- (ii) It is also present in nucleic acid (in DNA and RNA) which are the main components of phosphate rocks.
- (iii) Arsenic, antimony and bismuth are found mainly as sulphide minerals.

Electronic Configuration :

The valence shell electronic configuration of these elements is ns^2np^3 .

Atomic and Ionic Radii :

Covalent radius : $\text{N} < \text{P} < \text{As} < \text{Sb} < \text{Bi}$

Explanation :

Covalent and ionic (in a particular state) radii increase in size down the group. There is a considerable increase in covalent radius from N to P. However, from As to Bi only a small increase in covalent radius is observed. This is due to the presence of completely filled d and/or f orbitals in heavier members.

Ionisation Enthalpy :

$\text{N} > \text{P} > \text{As} > \text{Sb} > \text{Bi}$ (IE_1 values)

Explanation :

Ionisation enthalpy decreases down the group due to gradual increase in atomic size. Because of the extra stable half-filled p orbitals electronic configuration and smaller size, the ionisation enthalpy of the group 15 elements is much greater than that of group 14 elements in the corresponding periods. The order of successive ionisation enthalpies, as expected is $\Delta_1 H_1 < \Delta_1 H_2 < \Delta_1 H_3$ (See above table).

Electronegativity :

$\text{N} > \text{P} > \text{As} > \text{Sb} = \text{Bi}$
(1.9) (1.9)

Explanation :

The electronegativity value, in general, decreases down the group with increasing atomic size. However, amongst the heavier elements, the difference is not that much pronounced.

Metallic Character

$\frac{N < P}{\text{Non metal}}$	$\frac{As < Sb}{\text{Metalloid}}$	$\frac{Bi}{\text{Metals}}$
----------------------------------	------------------------------------	----------------------------

Physical Properties :

- All the elements of this group are polyatomic. Dinitrogen is a diatomic gas while all others are solids.
- Metallic character increases down the group.
- Nitrogen and phosphorus are non-metals, arsenic and antimony metalloids and bismuth is a metal. This is due to decrease in ionisation enthalpy and increase in atomic size.
- The boiling points, in general, increase from top to bottom in the group but the melting point increases upto arsenic and then decreases upto bismuth.
- Except nitrogen all the elements show allotropy.

P → exists in three allotropic form as white, red and black

As, Sb → exist as yellow and grey

Bi → exist as α , β , γ , δ allotropic form

Catenation

- * The group 15 elements also show catenation property but to much smaller extent than carbon. For example hydrazine (H_2NNH_2) has two N atoms bonded together HN_3 has three N atoms.



- * Among group 15 elements P has the maximum tendency for catenation forming cyclic as well as open chain compounds consisting of many phosphorous atoms.

P_2H_4 has two P atoms bonded together the lesser tendency of elements of group 15 to show catenation in comparison to carbon is their low dissociation enthalpies.

C – C	353.3 kJ / mole
N – N	160.8 kJ / mole
P – P	201.6 kJ / mole
As – As	147.4 kJ / mole

Chemical Properties :**Oxidation states and trends in chemical reactivity**

- The common oxidation states of these elements are -3 , $+3$ and $+5$.
- The tendency to exhibit -3 oxidation state decreases down the group due to increase in size and metallic character. Bismuth hardly forms any compound in -3 oxidation state.
- The stability of $+5$ oxidation state decreases down the group. The only well characterised Bi (V) compound is BiF_5 .

- (iv) The stability of +5 oxidation state decreases and that of +3 state increases (due to inert pair effect) down the group.
- (v) Nitrogen exhibits +1, +2, +4 oxidation states also when it reacts with oxygen. Phosphorus also shows +1 and +4 oxidation states in some oxoacids.
- (vi) In the case of nitrogen, all oxidation states from +1 to +4 tend to disproportionate in acid solution. For example,
- (i) $3\text{HNO}_2 \rightarrow \text{HNO}_3 + \text{H}_2\text{O} + 2\text{NO}$
- (vii) Similarly, in case of phosphorus nearly all intermediate oxidation states disproportionate into +5 and -3 both in alkali and acid.
- (ii) $4\text{H}_3\text{PO}_3 \xrightarrow{\text{Heat}} 3\text{H}_3\text{PO}_4 + \text{PH}_3$
- (viii) +3 oxidation state in case of arsenic, antimony and bismuth becomes increasingly stable with respect to disproportionation.
- (ix) Nitrogen is restricted to a maximum covalency of 4 since only four (one s and three p) orbitals are available for bonding.
- (x) The heavier elements have vacant d orbitals in the outermost shell which can be used for bonding (covalency) and hence, expand their covalency as in PF_6^- .

Anomalous properties of nitrogen

- (i) Nitrogen has unique ability to form $p_\pi - p_\pi$ multiple bonds with itself and with other elements having small size and high electronegativity (e.g., C, O).
- (ii) Heavier elements of this group do not form $p_\pi - p_\pi$ bonds as their atomic orbitals are so large and diffuse that they cannot have effective overlapping.
- (iii) Nitrogen exists as a diatomic molecule with a triple bond (one σ and two π) between the two atoms. N_2 bond enthalpy ($941.4 \text{ kJ mol}^{-1}$) is very high.
- (iv) Phosphorus, arsenic and antimony form single bonds as P-P, As-As and Sb-Sb while bismuth forms metallic bonds in elemental state.
- (v) The single N-N bond is weaker than the single P-P bond because of high interelectronic repulsion of the non-bonding electrons, owing to the small bond length. As a result the catenation tendency is weaker in nitrogen.
- (vi) Another factor which affects the chemistry of nitrogen is the absence of d orbitals in its valence shell. Besides restricting its covalency to four, nitrogen cannot form $d_\pi - p_\pi$ bond as the heavier elements can e.g., $\text{R}_3\text{P}=\text{O}$ or $\text{R}_3\text{P}=\text{CH}_2$ (R=alkyl group).
- (vii) Phosphorus and arsenic can form $d_\pi - d_\pi$ bond also with transition metals when their compounds like $\text{P}(\text{C}_2\text{H}_5)_3$ and $\text{As}(\text{C}_6\text{H}_5)_3$ act as ligands.

(i) Reactivity towards hydrogen:

All the elements of Group 15 form hydrides of the type EH_3 where $\text{E} = \text{N}, \text{P}, \text{As}, \text{Sb}$ or Bi . Some of the properties of these hydrides are shown in Table. The hydrides show regular gradation in their properties. The stability of hydrides decreases from NH_3 to BiH_3 which can be observed from their bond dissociation enthalpy. Consequently, the reducing character of the hydrides increases. Ammonia is only a mild reducing agent while BiH_3 is the strongest reducing agent amongst all the hydrides. Basicity also decreases in the order $\text{NH}_3 > \text{PH}_3 > \text{AsH}_3 > \text{SbH}_3 \geq \text{BiH}_3$.

Table : Properties of Hydrides of Group 15 Elements

Property	NH_3	PH_3	AsH_3	SbH_3	BiH_3
Melting point/K	195.2	139.5	156.7	185	—
Boiling point/K	238.5	185.5	210.6	254.6	290
(E–H)distance/pm	101.7	141.9	151.9	170.7	—
HEH angle ($^\circ$)	107.8	93.6	91.8	91.3	—
$\Delta_f H^\circ / \text{kJ mol}^{-1}$	–46.1	13.4	66.4	145.1	278
$\Delta_{\text{diss}} H^\circ (\text{E} - \text{H}) / \text{kJ mol}^{-1}$	389	322	297	255	—

(ii) Reactivity towards oxygen : All these elements form two types of oxides: E_2O_3 and E_2O_5 .


The oxide in the higher oxidation state of the element is more acidic than that of lower oxidation state. Their acidic character decreases down the group. The oxides of the type E_2O_3 of nitrogen and phosphorus are purely acidic, that of arsenic and antimony amphoteric and those of bismuth predominantly basic.

(iii) Reactivity towards halogens: These elements react to form two series of halides: EX_3 and EX_5 . Nitrogen does not form pentahalide due to non-availability of the d orbitals in its valence shell. Pentahalides are more covalent than trihalides. All the trihalides of these elements except those of nitrogen are stable. In case of nitrogen, only NF_3 is known to be stable. Trihalides except BiF_3 are predominantly covalent in nature.**(iv) Reactivity towards metals :** All these elements react with metals to form their binary compounds exhibiting –3 oxidation state, such as, Ca_3N_2 (calcium nitride) Ca_3P_2 (calcium phosphide), Na_3As (sodium arsenide), Zn_3Sb_2 (zinc antimonide) and Mg_3Bi_2 (magnesium bismuthide).**DINITROGEN****Preparation :****(a) Commercial preparation :**

Dinitrogen is produced **commercially** by the liquefaction and fractional distillation of air. Liquid dinitrogen (b.p. 77.2 K) distils out first leaving behind liquid oxygen (b.p. 90 K).


(b) Laboratory preparation :

(i) Dinitrogen is prepared by treating an aqueous solution of ammonium chloride with sodium nitrite.





Small amounts of NO and HNO_3 are also formed in this reaction; these impurities can be removed by passing the gas through aqueous sulphuric acid containing potassium dichromate.





(ii) Dinitrogen can also be obtained by the thermal decomposition of ammonium dichromate.





Note : Very pure nitrogen can be obtained by the thermal decomposition of sodium or barium azide.




(c) Other preparation




Cl_2 passed into liquid NH_3





In this method conc. of NH_3 should not be lowered down beyond a particular limit.



↓



(Tremendously explosive)

❑ **Physical properties :**


- Dinitrogen is a colourless, odourless, tasteless and non-toxic gas.
- Nitrogen atom has two stable isotopes: ^{14}N and ^{15}N .
- It has a very low solubility in water (23.2 cm^3 per litre of water at 273 K and 1 bar pressure)
- Dinitrogen has low freezing and boiling points.

❑ **Chemical properties**


Reaction with metal : At higher temperatures, it directly combines with some metals to form predominantly ionic nitrides and with non-metals, covalent nitrides. A few typical reactions are:



Reaction with metal : It combines with hydrogen at about 773 K in the presence of a catalyst (Haber's Process) to form ammonia:




Dinitrogen combines with dioxygen only at very high temperature (at about 2000 K) to form nitric oxide, NO.





Absorption on calcium carbide

N₂ can be absorbed by calcium carbide at the temperature around 1000°C.



It is a very good fertiliser.

**Qus. Why dinitrogen is inert at room temperature ?**

Ans. Dinitrogen is inert at room temperature because of the high bond enthalpy of N≡N bond. Reactivity, however, increases rapidly with rise in temperature.

TYPES OF NITRIDE :

Salt like or ionic : Li₃N, Na₃N, K₃N, Ca₃N₂, Mg₃N₂, Be₃N₂

Covalent : AlN, BN, Si₃N₄, Ge₃N₄, Sn₃N₄

Interstitial : MN $\underbrace{\text{(M = Sc, Ti, Zr, Hf, La)}}_{\text{HCP or FCC}}$

No of metal atom per unit cell is equal to no of octahedral voids per unit cell.

All the octahedral voids are occupied by nitrogen atoms. Hence the formula is MN.

HCP : Hexagonal closed packing


FCC : Face centred cubic

Uses :

- The main use of dinitrogen is in the manufacture of ammonia and other industrial chemicals containing nitrogen, (e.g., calcium cyanamide).
- It also finds use where an inert atmosphere is required (e.g., in iron and steel industry, inert diluent for reactive chemicals).
- Liquid dinitrogen is used as a refrigerant to preserve biological materials, food items and in cryosurgery.



AMMONIA**Preparation :**

- Ammonia is present in small quantities in air and soil where it is formed by the decay of nitrogenous organic matter e.g., urea.




- Small scale preparation

By the decomposition of ammonium salts when treated with caustic soda or calcium hydroxide.




- Large scale manufacturing (Haber's Process)



* According to Le Chatelier's principle, high pressure and low temperature would favour the formation of ammonia.

- * The optimum conditions for the production of ammonia are a pressure of 200×10^5 Pa (about 200 atm), a temperature of ~ 700 K.
- * Use of a catalyst such as iron oxide with small amounts of K_2O and Al_2O_3 to increase the rate of attainment of equilibrium.
- * The flow chart for the production of ammonia is shown in figure. Earlier, iron was used as a catalyst with molybdenum as a promoter.



Flow chart for the manufacture of ammonia


Other preparation :

- Nitrate or nitrite reduction : $NO_3^- / NO_2^- + Zn \text{ or } Al + NaOH \longrightarrow NH_3 + [Zn(OH)_4]^{2-}$ or $[Al(OH)_4]^-$
- Metal nitride hydrolysis : $N^{3-} + 3H_2O \longrightarrow NH_3 \uparrow + 3 OH^-$

Properties :

- Ammonia is a colourless gas with a pungent odour.
- Its freezing and boiling points are 198.4 and 239.7 K respectively.
- In the solid and liquid states, it is associated through hydrogen bonds as in the case of water and that accounts for its higher melting and boiling points than expected on the basis of its molecular mass.
- Ammonia gas is highly soluble in water.
- Basic character :**



Its aqueous solution is weakly basic due to the formation of OH^- ions.






It forms ammonium salts with acids, e.g., NH_4Cl , $(NH_4)_2 SO_4$, etc.

As a weak base, it precipitates the hydroxides (hydrated oxides in case of some metals) of many metals from their salt solutions.

For example,






In ammonia molecule the presence of a lone pair of electrons on the nitrogen atom of the makes it a Lewis base. It donates the electron pair and forms linkage with metal ions and the formation of such complex compounds finds applications in detection of metal ions such as Cu^{2+} , Ag^+ :



Other reactions


CH_3COOH is strong acid in liq. NH_3 while in water is weak acid.



Basicity order $\text{NH}_3 > \text{H}_2\text{O}$

more solvation of H^+ in NH_3 .

Hydrolysis and Ammonolysis occurs is a same way.



Rate of hydrolysis and Ammonolysis will be affected by the presence of HCl vapour & NH_4Cl vapour respectively.

Uses :

- (i) Ammonia is used to produce various nitrogenous fertilisers (ammonium nitrate, urea, ammonium phosphate and ammonium sulphate).
- (ii) In the manufacture of some inorganic nitrogen compounds, the most important one being nitric acid.
- (iii) Liquid ammonia is also used as a refrigerant.

BONDING IN AMMONIA :

The ammonia molecule is trigonal pyramidal with the nitrogen atom at the apex. It has three bond pairs and one lone pair of electrons.

OXIDES OF NITROGEN :







Nitrogen forms a number of oxides in different oxidation states. The names, formulas, preparation and physical appearance of these oxides are given in Table.

Oxides of Nitrogen





Name	Formula	Oxidation state of nitrogen	Common methods of preparation	Physical appearance and chemical nature
Dinitrogen oxide [Nitrogen (II) oxide]	N ₂ O	+1	$\text{NH}_4\text{NO}_3 \xrightarrow{\text{Heat}} \text{N}_2\text{O} + 2\text{H}_2\text{O}$	Colourless gas, neutral
Nitrogen monoxide [Nitrogen (II) oxide]	NO	+2	$2\text{NaNO}_2 + 2\text{FeSO}_4 + 3\text{H}_2\text{SO}_4 \rightarrow \text{Fe}_2(\text{SO}_4)_3 + 2\text{NaHSO}_4 + 2\text{H}_2\text{O} + 2\text{NO}$	Colourless gas, Neutral
Dinitrogen trioxide [Nitrogen (III) oxide]	N ₂ O ₃	+3	$2\text{NO} + \text{N}_2\text{O}_4 \xrightarrow{-30^\circ\text{C}} 2\text{N}_2\text{O}_3$	Pale Blue Solid (MP = -100.1°C), acidic, Intense blue liquid (-30°C)
Nitrogen dioxide [Nitrogen IV oxide]	NO ₂	+4	$2\text{Pb}(\text{NO}_3)_2 \xrightarrow{673\text{K}} 4\text{NO}_2 + 2\text{PbO} + \text{O}_2$	brown gas, acidic
Dinitrogen tetroxide [Nitrogen (IV) oxide]	N ₂ O ₄	+4	$2\text{NO}_2 \xrightleftharpoons[\text{Heat}]{\text{Cool}} \text{N}_2\text{O}_4$	Colourless solid/ liquid acidic
Dinitrogen Pentaoxide [Nitrogen (V) oxide]	N ₂ O	+5	$4\text{HNO}_3 + \text{P}_4\text{O}_{10} \rightarrow 4\text{HPO}_3 + 2\text{N}_2\text{O}_5$	Colourless Solid, acidic

Structure of Oxides of Nitrogen




Formula	Resonance Structures	Bond Parameters
N ₂ O	$\ddot{\text{N}}=\text{N}=\ddot{\text{O}} \leftrightarrow :\text{N}\equiv\text{N}-\ddot{\text{O}}:$	$\begin{array}{c} \text{N} - \text{N} - \text{O} \\ 113 \text{ pm} \quad 119 \text{ pm} \\ \text{Linear} \end{array}$
NO	$:\text{N}=\ddot{\text{O}} \leftrightarrow :\ddot{\text{N}}=\ddot{\text{O}}:$	$\begin{array}{c} \text{N} - \text{O} \\ 115 \text{ pm} \end{array}$
N ₂ O ₃		
NO ₂		$\begin{array}{c} \text{O} - \text{N} - \text{O} \\ 134^\circ \quad 120 \text{ pm} \\ \text{Angular} \end{array}$
N ₂ O ₄		$\begin{array}{c} \text{O} - \text{N} - \text{O} \\ 135^\circ \quad 175 \text{ pm} \\ \text{Planar} \end{array} \quad \begin{array}{c} \text{O} - \text{N} - \text{O} \\ 121 \text{ pm} \end{array}$
N ₂ O ₅		$\begin{array}{c} \text{O} - \text{N} - \text{O} \\ 151 \text{ pm} \quad 112^\circ \\ \text{Planar} \end{array} \quad \begin{array}{c} \text{O} - \text{N} - \text{O} \\ 119 \text{ pm} \quad 134^\circ \end{array}$







Preparation :**1. N₂O****2. NO**

Industrial process.


**3. N₂O₃****4. NO₂**

M = Pb, Cu, Ba, Ca







**5. N₂O₅**

Properties :**(I) Decomposition Behaviour****(II) Reaction with H_2O & NaOH**



	H_2O	NaOH
(i) N_2O :	Fairly soluble in water and produces neutral solution	-----
(ii) NO :	Sparingly soluble in water and produces neutral sol ⁿ .	-----
(iii) N_2O_3 :	2HNO_2 Hence it is known as anhydride of HNO_2	NaNO_2
(iv) NO_2 :	$\text{HNO}_2 + \text{HNO}_3$ called as mixed anhydride	$\text{NaNO}_2 + \text{NaNO}_3$
(v) N_2O_5 :	2HNO_3 called as anhydride of HNO_3	NaNO_3

Other properties :

Hence, it is a better supporter for combustion.





(ii) It supports combustion also for molten sulphur and hot phosphorous.






(iii) It is being absorbed by FeSO_4 solution.

(iv) It is having reducing property.




(v) NO shows oxidising property also.








(Used for NH_2OH preparation)

(vi) NO combines with X_2 ($\text{X} = \text{Cl}, \text{Br}, \text{F}$) to produce NOX





N_2O_3 : No more properties.

NO_2 : (1) It is having oxidising property.




NO not formed : $2\text{KI} + 2\text{NO}_2 \longrightarrow \text{I}_2 + 2\text{KNO}_2$

(2) Reducing property of NO_2 .






not the reduction product of O_3

N_2O_5 :



I_2O_5 is used for the estimation of CO




This proves that N_2O_5 is consisting of ion pair of NO_2^+ & NO_3^-

OXOACIDS OF NITROGEN

$\text{H}_2\text{N}_2\text{O}_2$ (hyponitrous acid), HNO_2 (nitrous acid) and HNO_3 (nitric acid). Amongst them HNO_3 is the most important.






NITROUS ACID (HNO_2)

Preparation





Properties


- (a) **Oxidising property** : Because of its easy oxidation to liberate nascent oxygen, it acts as a strong oxidant $2\text{HNO}_2 \longrightarrow \text{H}_2\text{O} + 2\text{NO} + (\text{O})$




- (b) **Reducing property** : Nitrous acid also acts as a reducing agent as it can be oxidised into nitric acid.





- (c) **Reaction with NH_3 / $-\text{NH}_2$ compounds :**



Urea



Benzene diazonium chloride




NITRIC ACID

It was named aqua fortis (means strong water) by alchemists.


Preparation :

Laboratory Method : By heating KNO_3 or NaNO_3 and concentrated H_2SO_4 in a glass retort.




Large scale preparation (Ostwald's process) :


(i) This method is based upon catalytic oxidation of NH_3 by atmospheric oxygen.



(ii) Nitric oxide thus formed combines with oxygen giving NO_2 .





(iii) Nitrogen dioxide so formed, dissolves in water to give HNO_3 .



NO thus formed is recycled and the aqueous HNO_3 can be concentrated by distillation upto ~ 68% by mass. Further concentration to 98% can be achieved by dehydration with concentrated H_2SO_4 .

Birkeland Eyde Process or arc process



Properties


Physical properties

It has extremely corrosive action on the skin and causes painful sores.

(i) It is a colourless liquid (f.p. 231.4 K and b.p. 355.6 K).

(ii) Laboratory grade nitric acid contains ~ 68% of the HNO_3 by mass and has a specific gravity of 1.504.


(iii) Nitric acid usually acquires yellow or brown colour due to its decomposition by sunlight into NO_2 .



The yellow or brown colour of the acid can be removed by warming it to 60-80°C and bubbling dry air through it.

Chemical properties

Acidic character in aqueous solution, nitric acid behaves as a strong acid giving hydronium and nitrate ions.



Oxidising nature: Nitric acid acts as a strong oxidising agent as it decomposes to give nascent oxygen easily.




or



(i) **Oxidation of non-metals :** The nascent oxygen oxidises various non-metals to their corresponding oxyacids of highest oxidation state.

- (1) Sulphur is oxidised to sulphuric acid



- (2) Carbon is oxidised to carbonic acid



- (3) Phosphorus is oxidised to orthophosphoric acid.



conc. and hot

- (4) Iodine is oxidised to iodic acid



conc. and hot

(ii) Oxidation of metalloids

Metalloids like non-metals also form oxyacids of highest oxidation state.

- (1) Arsenic is oxidised to arsenic acid



or $\text{As} + 5\text{HNO}_3 \xrightarrow{\text{conc. and hot}} \text{H}_3\text{AsO}_4 + 5\text{NO}_2 + \text{H}_2\text{O}$

conc. and hot

- (2) Antimony is oxidised to antimononic acid




conc. and hot

- (3) Tin is oxidised to meta-stannic acid.




(iii) Oxidation of Compounds:


- (1) Sulphur dioxide is oxidised to sulphuric acid



- (2) Hydrogen sulphide is oxidised to sulphur




- (3) Ferrous sulphate is oxidised to ferric sulphate in presence of H_2SO_4



- (4) Iodine is liberated from KI.



- (5) HBr, HI are oxidised to Br_2 and I_2 , respectively.




- (6) Ferrous sulphide is oxidised to ferric sulphate



- (7) Stannous chloride is oxidised to stannic chloride in presence of HCl.



Hydroxylamine




(8) Oxidation of organic compounds.

Sawdust catches fire when nitric acid is poured on it.




Turpentine oil bursts into flames when treated with fuming nitric acid.

Toluene is oxidised to benzoic acid with dil. HNO_3 .

Cane sugar is oxidised to oxalic acid.







(ii) **Reaction with metal** concentrated nitric acid is a strong oxidising agent and attacks most metals except noble metals such as gold and platinum. Au & Pt dissolve in aqua regia a mixture of 25% conc. HNO_3 & 75% conc. HCl . The products of oxidation depend upon the concentration of the acid, temperature and the nature of the material undergoing oxidation.



Some metals (e.g., Cr, Al) do not dissolve in concentrated nitric acid because of the formation of a passive film of oxide on the surface.

Armstrong postulated that primary action of nitric acid is to produce hydrogen in the nascent form. Before this hydrogen is allowed to escape, it reduces the nitric acid into number of products like NO_2 , NO , N_2O , N_2 or NH_3 according to the following reactions :



The progress of the reaction is controlled by a number of factors :

- the nature of the metal,
- the concentration of the acid,
- the temperature of the reaction,
- the presence of other impurities.

Concentration of nitric acid	Metal	Main Products
Very dilute HNO_3 (6%)	Mg, Mn	H_2 + Metal nitrate
	Fe, Zn, Sn	NH_4NO_3 + metal nitrate + H_2O
	Pb, Cu, Ag, Hg	NO + metal nitrate + H_2O

Dilute HNO_3 (20%)	Fe, Zn	$\text{N}_2\text{O} + \text{metal nitrate} + \text{H}_2\text{O}$
	Sn	$\text{NH}_4\text{NO}_3 + \text{Sn}(\text{NO}_3)_2$
Conc. HNO_3 (70%)	Zn, Fe, Pb, Cu, Ag	$\text{NO}_2 + \text{metal nitrate} + \text{H}_2\text{O}$
	Sn	$\text{NO}_2 + \text{H}_2\text{SnO}_3$ Metastannic acid

Action on Proteins :




Nitric acid attacks proteins forming a yellow nitro compound called xanthoprotein. It, therefore, stains skin and renders wool yellow. This property is utilized for the test of proteins.

Uses : The major use of nitric acid is in the manufacture of ammonium nitrate for fertilisers and other nitrates for use in explosives and pyrotechnics. It is also used for the preparation of nitroglycerin, trinitrotoluene and other organic nitro compounds. Other major uses are in the **pickling of stainless steel**, etching of metals and as an oxidiser in rocket fuels.






Pickling is a metal surface treatment used to remove impurities, such as stains, inorganic contaminants, rust or scale from ferrous metals, copper, precious metals and aluminium alloys. A solution called pickle liquor, which contains strong acids, is used to remove surface impurities.

ALLOTROPIC FORMS OF PHOSPHORUS**Comparison between White and Red Phosphorus**



Property	White phosphorus	Red phosphorus
Physical state	Soft waxy solid.	Brittle powder.
Colour	White when pure. Attains yellow colour on standing.	Red.
Odour	Garlic	Odourless.
Solubility in water	Insoluble.	insoluble
Solubility in CS_2	Soluble.	Insoluble.
Physiological action	Poisonous.	Non-poisonous.
Chemical activity	Very active.	Less active.
Stability	Unstable.	Stable.
Phosphorescence	Glow in dark	Does not glow in dark.
Molecular formula	P_4	Complex polymer.

Preparation of white 'P'**Reactions of 'P'**


* Reaction with hot metal —

**PHOSPHINE****Preparation**




(i) Phosphine is prepared by the reaction of calcium phosphide with water or dilute HCl.



(ii) Laboratory preparation it is prepared by heating white phosphorus with concentrated NaOH solution in an inert atmosphere of CO_2 .



Pure PH_3 is non inflammable but becomes inflammable owing to the presence of P_2H_4 or P_4 vapours. To purify it from the impurities, it is absorbed in HI to form phosphonium iodide (PH_4I) which on treating with KOH gives off phosphine.



Other preparation

Physical Properties :





- (i) It is a colourless gas with rotten fish smell and is highly poisonous.
- (ii) It explodes in contact with traces of oxidising agents like HNO_3 , Cl_2 and Br_2 vapours.
- (iii) It is slightly soluble in water but soluble in CS_2 . The solution of PH_3 in water decomposes in presence of light giving red phosphorus and H_2 .

Chemical Properties :


- (i) It absorbed in copper sulphate or mercuric chloride solution, the corresponding phosphides are obtained.



Phosphine is weakly basic and like ammonia, gives phosphonium compounds with acids e.g.,



yellow ppt.



Black ppt.





white/colourless solid

which is used for making



fire-proof cotton fabrics

Note :

Like NH_3 , PH_3 also can form addition product.



PH_3 can be absorbed by $\text{Ca}(\text{OCl})\text{Cl}$.

**Uses :**


- (i) The spontaneous combustion of phosphine is technically used in Holme's signals. Containers containing calcium carbide and calcium phosphide are pierced and thrown in the sea when the gases evolved burn and serve as a signal.
- (ii) It is also used in smoke screens.

PHOSPHORUS HALIDES

Phosphorus forms two types of halides, PX_3 ($X = F, Cl, Br, I$) and PX_5 ($X = F, Cl, Br$).

PHOSPHORUS TRICHLORIDE**Preparation**

- (i) By passing dry chlorine over heated white phosphorus.





- (ii) By the action of thionyl chloride with white phosphorus.

**Properties**


- (i) It is a colourless oily liquid
 (ii) Hydrolyses in the presence of moisture.

$$PCl_3 + 3H_2O \rightarrow H_3PO_3 + 3HCl$$


 (iii) It reacts with organic compounds containing $-OH$ group such as CH_3COOH , C_2H_5OH .

**PHOSPHORUS PENTACHLORIDE****Preparation**

- (i) By the reaction of white phosphorus with excess of dry chlorine.



- (ii) By the action of SO_2Cl_2 on phosphorus.

**Properties :**

- (i) PCl_5 is a yellowish white powder
 (ii) It hydrolyses in moist air to $POCl_3$ and finally gets converted to phosphoric acid.

$$PCl_5 + H_2O \rightarrow POCl_3 + 2HCl$$

$$POCl_3 + 3H_2O \rightarrow H_3PO_4 + 3HCl$$

 (iii) When heated, it sublimes but decomposes on stronger heating.

$$PCl_5 \xrightarrow{\text{Heat}} PCl_3 + Cl_2$$

 (iv) It reacts with organic compounds containing $-OH$ group converting them to chloro derivatives.

$$C_2H_5OH + PCl_5 \rightarrow C_2H_5Cl + POCl_3 + HCl$$

$$CH_3COOH + PCl_5 \rightarrow CH_3COCl + POCl_3 + HCl$$

 (v) Finely divided metals on heating with PCl_5 give corresponding chlorides.

$$2Ag + PCl_5 \rightarrow 2AgCl + PCl_3$$


$$Sn + 2PCl_5 \rightarrow SnCl_4 + 2PCl_3$$

Uses :

It is used in the synthesis of some organic compounds, e.g., C_2H_5Cl , CH_3COCl .

Note :

In gaseous and liquid phases, it has a trigonal bipyramidal structure as shown. The three equatorial $P-Cl$ bonds are equivalent, while the two axial bonds are longer than equatorial bonds. This is due to the fact that the axial bond pairs suffer more repulsion as compared to equatorial bond pairs.




In the solid state it exists as an ionic solid, $[PCl_4]^+[PCl_6]^-$ in which the cation, $[PCl_4]^+$ is tetrahedral and the anion, $[PCl_6]^-$ is octahedral.

OXIDES OF PHOSPHORUS


It forms two important oxides which exist in dimeric forms.

PHOSPHORUS TRIOXIDE (P₄O₆)**Preparation**

Phosphorus trioxides is formed when phosphorus is burnt in a limited supply of air and inert atmosphere.


**Properties**

- (a) **Heating in air :** On heating in air, it forms phosphorus pentoxide.



Phosphorus (V) oxide

- (b) **Action of water :** It dissolves in cold water to give phosphorus acid.



Phosphorus acid

It is, therefore, considered as anhydride of phosphorus acid.

Note: With hot water, it gives phosphoric acid and inflammable phosphine.

Structure

- (a) Each atom of phosphorus in P₄O₆ is present at the corner of a tetrahedron
 (b) Each phosphorus atom is covalently bonded to three oxygen atoms and each oxygen atom is bonded to two phosphorus atoms.
 (c) It is clear from the structure that the six oxygen atoms lie along the edges of the tetrahedron of P atoms.

PHOSPHORUS (V) OXIDE (P₄O₁₀)

Preparation : It is prepared by heating white phosphorus in excess of air.

**Properties**

- (a) It is snowy white solid.
 (b) **Action with water :** It readily dissolves in cold water forming metaphosphoric acid.




Metaphosphoric acid.

With hot water it gives phosphoric acid.




Phosphoric acid


- (c) **Dehydrating nature :** Phosphorus pentoxide has strong affinity for water and, therefore, acts as a powerful dehydrating agent. It extracts water from many inorganic and organic compounds.



- (d) P_4O_{10} is a very strong dehydrating agent and extracts water from many compounds including sulphuric acid and nitric acid.



Chlorine (VII) oxide



Acetamide

Methyl cyanide

Structure

- (a) Its structure is similar to that of P_4O_6 .
- (b) In addition, each phosphorus atom forms a double bond with oxygen atom as shown in figure.

OXOACIDS OF PHOSPHORUS :

The important oxoacids of phosphorus with their formulae, methods of preparation and the presence of some characteristic bonds in their structures are given in a table.

Oxoacids of Phosphores				
Name	Formula	Oxidation state of Phosphorus	Characteristics bonds and their number	Preparation
Hypophosphorus (Phosphinic)	H_3PO_2	+1	One P – OH Two P – H One P = O	White P_4 + alkali
Orthophosphorous (Phosphonic)	H_3PO_3	+3	Two P – OH One P – H	$P_2O_3 + H_2O$
Pyrophosphorous	$H_4P_2O_5$	+3	Two P – OH Two P – H Two P = O	$PCl_3 + H_3PO_3$
Hypophosphoric	$H_4P_2O_6$	+4	Four P – OH Two P = O One P – P	red P_4 + alkali
Orthophosphoric	H_3PO_4	+5	Three P – OH One P = O	$P_4O_{10} + H_2O$
Pyrophosphoric	$H_4P_2O_7$	+5	Four P – OH Two P = O	Heat Phosphoric acid
Metaphosphoric	$(HPO_3)_n$	+5	Three P – OH Three P = O Three P – O – P	phosphorous acid + Br_2 , heat in a sealed tube

STRUCTURE OF OXO ACID :




In oxoacids phosphorus is tetrahedrally surrounded by other atoms. All these acids contain at least one P=O bond and one P–OH bond. The oxoacids in which phosphorus has lower oxidation state (less than +5) contain, in addition to P=O and P–OH bonds, either P–P (e.g., in $\text{H}_4\text{P}_2\text{O}_6$) or P–H (e.g., in H_3PO_2) bonds but not both. H_3PO_3 and H_3PO_2 are diacidic and monobasic respectively.

Note : -


- (i) These acids in +3 oxidation state of phosphorus tend to disproportionate to higher and lower oxidation states. For example, phosphorous acid on heating disproportionates to give orthophosphoric acid (or phosphoric acid) and phosphine.



- (ii) The acids which contain P–H bond have strong reducing properties. Thus, hypophosphorous acid is a good reducing agent as it contains two P–H bonds and reduces, AgNO_3 to metallic silver.

**Heating Effect :****Graham salt**

Graham's salt is the best known of these long chain polyphosphates, and is formed by quenching molten NaPO_3 . Graham's salt is soluble in water. These solutions give precipitates with metal ions such as Pb^{2+} and Ag^+ but not with Ca^{2+} and Mg^{2+} . Graham's salt is sold commercially under the trade name Calgon. In industry it is incorrectly called sodium hexametaphosphate crystallizing. It is widely used for softening water.



OXYGEN FAMILY

GROUP 16 ELEMENTS (O, S, Se, Te, Po)

This is sometimes known as group of chalcogens.

❑ Occurrence

Oxygen is the most abundant of all the elements on earth crust. Oxygen forms about 46.6% by mass of earth's crust. Dry air contains 20.946% oxygen by volume. However, the abundance of sulphur in the earth's crust is only 0.03-0.1%. Combined sulphur exists primarily as sulphates such as gypsum $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, epsom salt $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$, baryte BaSO_4 and sulphides such as galena PbS , zinc blende ZnS , copper pyrites CuFeS_2 . Traces of sulphur occur as hydrogen sulphide in volcanoes. Organic materials such as eggs, proteins, garlic, onion, mustard, hair and wool contain sulphur.

Selenium and tellurium are also found as metal selenides and tellurides in sulphide ores. Polonium occurs in nature as a decay product of thorium and uranium minerals.

❑ Electronic Configuration

ns^2np^4 is the general valence shell electronic configuration.

❑ **Atomic and Ionic Radii :** Covalent radius : $\text{O} < \text{S} < \text{Se} < \text{Te}$

❑ **Ionisation Enthalpy :** $\text{O} > \text{S} > \text{Se} > \text{Te} > \text{Po}$ (IE_1 values)

❑ **Most Negative Electron Gain Enthalpy:** $\text{S} > \text{Se} > \text{Te} > \text{Po} > \text{O}$

❑ **Electronegativity :** $\text{O} > \text{S} > \text{Se} > \text{Te}$

❑ **Metallic Character :** $\text{O} < \text{S} < \text{Se} < \text{Te} < \text{Po}$

❑ **Melting and Boiling points :**

M.P. : $\text{Te} > \text{Po} > \text{Se} > \text{S} > \text{O}$

B.P. : $\text{Te} > \text{Po} > \text{Se} > \text{S} > \text{O}$

Elemental State

Oxygen exist as diatomic molecular gas in this case there is $p\pi - p\pi$ overlap thus two O atoms form double bond $\text{O} = \text{O}$. The intermolecular forces in O_2 are weak VB forces. $\therefore \text{O}_2$ exist as gas. On the other hand, other elements of family do not form stable $p\pi - p\pi$ bonds and do not exist as M_2 molecules. Other atoms are linked by single bonds and form poly atomic complex molecules for eg. $\text{S} - \text{S}_8$, $\text{Se} - \text{Se}_8$

Allotropy

All element exhibit allotropy for e.g.

Oxygen – O_2 and O_3

Liquid O_2 - pale blue

Solid O_2 - blue

❑ Physical Properties

- (i) Oxygen and sulphur are non-metals, selenium and tellurium metalloids, whereas polonium is a metal.
- (ii) Polonium is radioactive and is short lived (Half-life 13.8 days).
- (iii) All these elements exhibit allotropy.
- (iv) The melting and boiling points increase with an increase in atomic number down the group. The large difference between the melting and boiling points of oxygen and sulphur may be explained on the basis of their atomicity; oxygen exists as diatomic molecule (O_2) whereas sulphur exists as polyatomic molecule (S_8).

❑ Chemical Properties**Oxidation states and trends in chemical reactivity :**

- (i) The stability of -2 oxidation state decreases down the group. Polonium hardly shows -2 oxidation state.
- (ii) Electronegativity of oxygen is very high, it shows only negative oxidation state as -2 except Oxygen shows oxidation states of +2 and +1 in oxygen fluorides OF_2 and O_2F_2 respectively.
- (iii) Elements of the group exhibit +2, +4, +6 oxidation states but +4 and +6 are more common.
- (iv) Sulphur, selenium and tellurium usually show +4 oxidation state in their compounds with oxygen and +6 with fluorine.
- (v) The stability of +6 oxidation state decreases down the group and stability of +4 oxidation state increases (inert pair effect).
- (vi) Bonding in +4 and +6 oxidation states is primarily covalent.

❑ Anomalous behaviour of oxygen

The anomalous behaviour of oxygen, like other members of p-block present in second period is due to its small size and high electronegativity. One typical example of effects of small size and high electronegativity is the presence of strong hydrogen bonding in H_2O which is not found in H_2S . The absence of d orbitals in oxygen limits its covalency to four and in practice, rarely exceeds two. On the other hand, in case of other elements of the group, the valence shells can be expanded and covalency exceeds four.

(I) Reactivity with hydrogen:

- (i) All the elements of Group 16 form hydrides of the type H_2E ($E = O, S, Se, Te, Po$).
- (ii) Their acidic character increases from H_2O to H_2Te . The increase in acidic character can be explained in terms of decrease in bond enthalpy for the dissociation of H-E bond down the group. Owing to the decrease in enthalpy for the dissociation of H-E bond down the group, the thermal stability of hydrides also decreases from H_2O to H_2Po .
- (iii) All the hydrides except water possess reducing property and this character increases from H_2S to H_2Te .

Properties of Hydrides of Group 16 Elements

Property	H ₂ O	H ₂ S	H ₂ Se	H ₂ Te
m.p./K	273	188	208	222
b.p./K	373	213	232	269
H–E distance/pm	96	134	146	169
HEH angle (°)	104	92	91	90
$\Delta_f H / \text{kJ mol}^{-1}$	–286	–20	73	100
$\Delta_{\text{diss}} H(\text{H} - \text{E}) / \text{kJ mol}^{-1}$	463	347	276	238
Dissociation constant ^a	1.8×10^{-16}	1.3×10^{-7}	1.3×10^{-4}	2.3×10^{-3}

(II) Reactivity with oxygen :

- All these elements form oxides of the EO₂ and EO₃ types where E = S, Se, Te or Po.
- Ozone (O₃) and sulphur dioxide (SO₂) are gases while selenium dioxide (SeO₂) is solid.
- Reducing property of dioxide decreases from SO₂ to TeO₂; SO₂ is reducing while TeO₂ is an oxidising agent.
- Besides EO₂ type, sulphur, selenium and tellurium also form EO₃ type oxides (SO₃, SeO₃, TeO₃). Both types of oxides are acidic in nature.

(III) Reactivity towards the halogens:


- Elements of Group 16 form a large number of halides of the type, EX₆, EX₄ and EX₂ where E is an element of the group and X is a halogen.
- The stability of the halides decreases in the order F[–] > Cl[–] > Br[–] > I[–].
- Amongst hexahalides, hexafluorides are the only stable halides. All hexafluorides are gaseous in nature. They have octahedral structure. Sulphur hexafluoride, SF₆ is exceptionally stable for steric reasons.

Amongst tetrafluorides, SF₄ is a gas, SeF₄ a liquid and TeF₄ a solid. These fluorides have *sp*³*d* hybridisation and thus, have trigonal bipyramidal structures in which one of the equatorial positions is occupied by a lone pair of electrons. This geometry is also regarded as see-saw geometry. All elements except oxygen form dichlorides and dibromides (because they form oxides). These dihalides are formed by *sp*³ hybridisation and thus, have tetrahedral structure. The well known monohalides are dimeric in nature. Examples are S₂F₂, S₂Cl₂, S₂Br₂, Se₂Cl₂ and Se₂Br₂. These dimeric halides undergo disproportionation as given below : $2\text{Se}_2\text{Cl}_2 \rightarrow \text{SeCl}_4 + 3\text{Se}$



DIOXYGEN

(a) Laboratory method

(i) By heating oxygen containing salts such as chlorates, nitrates and permanganates.



(ii) By the thermal decomposition of the oxides of metals low in the electrochemical series and higher oxides of some metals.



(iii) Hydrogen peroxide is readily decomposed into water and dioxygen by catalysts such as finely divided metals and manganese dioxide.








(b) **Large scale preparation** : It can be prepared from water or air. Electrolysis of water leads to the release of hydrogen at the cathode and oxygen at the anode.



(c) **Industrially method** : Dioxygen is obtained from air by first removing carbon dioxide and water vapour and then, the remaining gases are liquefied and fractionally distilled to give dinitrogen and dioxygen.

Properties

- (i) Dioxygen is a colourless and odourless gas.
- (ii) Its solubility in water is to the extent of 3.08 cm³ in 100 cm³ water at 293 K which is just sufficient for the vital support of marine and aquatic life.
- (iii) It liquefies at 90 K and freezes at 55 K.
- (iv) Oxygen atom has three stable isotopes: ¹⁶O, ¹⁷O and ¹⁸O. Molecular oxygen, O₂ is unique in being paramagnetic inspite of having even number of electrons.
- (v) Dioxygen directly reacts with nearly all metals and non-metals except some metals (e.g., Au, Pt) and some noble gases. Its combination with other elements is often strongly exothermic which helps in sustaining the reaction. However, to initiate the reaction, some external heating is required as bond dissociation enthalpy of oxygen-oxygen double bond is high (493.4 kJ mol⁻¹). Some of the reactions of dioxygen with metals, non-metals and other compounds are as follows :



Some compounds are catalytically oxidised. For example,




- Uses :**
- (i) It's importance in normal respiration and combustion processes, oxygen is used in oxyacetylene welding, in the manufacture of many metals, particularly steel.
 - (ii) Oxygen cylinders are widely used in hospitals, high altitude flying and in mountaineering.
 - (iii) The combustion of fuels, e.g., hydrazines in liquid oxygen, provides tremendous thrust in rockets.

SIMPLE OXIDES

A binary compound of oxygen with another element is called oxide. In many cases one element forms two or more oxides. The oxides vary widely in their nature and properties. Oxides can be simple (e.g., MgO, Al₂O₃) or mixed (Pb₃O₄, Fe₃O₄).


Types of simple oxide : Simple oxides can be classified on the basis of their acidic, basic or amphoteric character.

Acidic oxide : An oxide that combines with water to give an acid is termed acidic oxide (e.g., SO₂, Cl₂O₇, CO₂, N₂O₅). For example, SO₂ combines with water to give H₂SO₃, an acid.




As a general rule, only non-metal oxides are acidic but oxides of some metals in high oxidation state also have acidic character (e.g., Mn₂O₇, CrO₃, V₂O₅).

Basic oxide : The oxides which give a base with water are known as basic oxides (e.g., Na₂O, CaO, BaO). In general, metallic oxides are basic. For example, CaO combines with water to give Ca(OH)₂, a base.



Amphoteric oxide :

Some metallic oxides exhibit a dual behaviour. They show characteristics of both acidic as well as basic oxides. Such oxides are known as amphoteric oxides. They react with acids as well as alkalies. For example, Al₂O₃ reacts with acids as well as alkalies.



Neutral oxide:

There are some oxides which are neither acidic nor basic. Such oxides are known as neutral oxides. Examples of neutral oxides are CO, NO and N₂O.


OZONE

(i) Ozone is an allotropic form of oxygen and is diamagnetic.

(ii) It is too reactive to remain for long in the atmosphere at sea level. At a height of about 20 kilometres, it is formed from atmospheric oxygen in the presence of sunlight. This ozone layer protects the earth's surface from an excessive concentration of ultraviolet (UV) radiations.

Threats to ozone layer

(i) Experiments have shown that nitrogen oxides (particularly nitric oxide) combine very rapidly with ozone and there is, thus, the possibility that nitrogen oxides emitted from the exhaust systems of supersonic jet aeroplanes might be slowly depleting the concentration of the ozone layer in the upper atmosphere.



(ii) Another threat to this ozone layer is probably posed by the use of freons which are used in aerosol sprays and as refrigerants.

Preparation

When a slow dry stream of oxygen is passed through a silent electrical discharge, conversion of oxygen to ozone (10%) occurs. The product is known as ozonised oxygen.




Since the formation of ozone from oxygen is an **endothermic** process, it is necessary to use a silent electrical discharge in its preparation to prevent its decomposition. If concentration of ozone greater than 10 percent is required, a battery of ozonisers can be used, and pure ozone (b.p. -112.4°C) can be condensed in a vessel surrounded by liquid oxygen.

Ques. Ozone is thermodynamically unstable with respect to oxygen. Explain ?

Sol. Because its decomposition into oxygen results in the liberation of heat (ΔH is negative) and an increase in entropy (ΔS is positive). These two effects reinforce each other, resulting in large negative Gibbs energy change (ΔG) for its conversion into oxygen.

Note :



Properties

- (i) Pure ozone is a pale blue gas, dark blue liquid and violet-black solid.
- (ii) Ozone has a characteristic fishy smell and in small concentrations it is harmless.

Toxic effect :

- (a) Toxic enough (more toxic than KCN). Its intense blue colour is due to the absorption of red light.
- (b) However, if the concentration rises above about 100 parts per million, breathing becomes uncomfortable resulting in headache and nausea.


Oxidizing properties

It is one of best oxidising agent, in acid solution, its standard, reduction potential value is 2.07 V.



It is next to F_2 . [above 2.07 V, only F_2 , F_2O are there]

It is not really surprising, therefore, high concentrations of ozone can be dangerously explosive. Due to the ease with which it liberates atoms of nascent oxygen ($O_3 \rightarrow O_2 + O$), it acts as a powerful oxidising agent. For example, it oxidises lead sulphide to lead sulphate and iodide ions to iodine.




- (i) Metal Sulphides to Sulphates.






- (ii) $2HX + O_3 \longrightarrow X_2 + H_2O + O_2 \quad [X = Cl, Br, I]$



- (iii) $NaNO_2 + O_3 \longrightarrow NaNO_3 + O_2$












- (iv) Moist S, P, As + $O_3 \Rightarrow$





- (v) Moist $I_2 \longrightarrow HIO_3$ whereas dry iodine $\longrightarrow I_4O_9$ (yellow)









} O_3 is estimated by this reaction



(viii) Hg loses its fluidity (tailing of Hg)




Brown



In all above reaction O_3 gives up O_2 but some reactions are there which consumes all O-atom.



Bonding in ozone : In ozone the two oxygen-oxygen bond lengths in the ozone molecule are identical (128 pm) and the molecule is angular as expected with a bond angle of about 117° . It is a resonance hybrid of two main forms given below:



Absorbent : (i) Turpentine oil (ii) Oil of cinnamon

Quantitative method for the estimating on Ozone : Ozone reacts with an excess of potassium iodide solution buffered with a borate buffer (pH 9.2), iodine is liberated which can be titrated against a standard solution of sodium thiosulphate.

Uses : (i) Sterilising water

(ii) Detection of position of the double bond in the unsaturated compound.

(iii) It is used as a germicide, disinfectant and for sterilising water.

(iv) It is also used for bleaching oils, ivory, flour, starch, etc.


(v) It acts as an oxidising agent in the manufacture of potassium permanganate.

❑ HYDROGEN PEROXIDE (H₂O₂)


Hydrogen peroxide is an important chemical used in pollution control treatment of domestic and industrial effluents.

Preparation


It can be prepared by the following methods.





(ii) Acidifying barium peroxide and removing excess water by evaporation under reduced pressure gives hydrogen peroxide.




Instead of H₂SO₄, H₃PO₄ is added now-a-days because H₂SO₄ catalyses the decomposition of H₂O₂ whereas H₃PO₄ favours to restore it.




(iii) Peroxodisulphate, obtained by electrolytic oxidation of acidified sulphate solutions at high current density, on hydrolysis yields hydrogen peroxide.



This method is now used for the laboratory preparation of D₂O₂.



(iii) Industrially it is prepared by the autooxidation of 2-alkylanthraquinols.



In this case 1% H₂O₂ is formed. It is extracted with water and concentrated to ~30% (by mass) by distillation under reduced pressure. It can be further concentrated to ~85% by careful distillation under low pressure. The remaining water can be frozen out to obtain pure H₂O₂.

♦ Physical Properties

In the pure state H_2O_2 is an almost colourless (very pale blue) liquid. Its important physical properties are given in Table. H_2O_2 is miscible with water in all proportions and forms a hydrate $\text{H}_2\text{O}_2 \cdot \text{H}_2\text{O}$ (mp 221K). A 30% solution of H_2O_2 is marketed as '100 volume' hydrogen peroxide. It means that one millilitre of 30% H_2O_2 solution will give 100 mL of oxygen at STP. Commercially marketed sample is 10 V, which means that the sample contains 3% H_2O_2 .


30% (w / v) or "100 V" H_2O_2 solution is called **per hydrol**.

Problem

Calculate the strength of 10 volume solution of hydrogen peroxide.

Solution

10 volume solution of H_2O_2 means that 1L of this H_2O_2 solution will give 10 L of oxygen at STP



On the basis of above equation 22.7 L of O_2 is produced from 68 g H_2O_2 at STP 10 L of O_2 at STP is produced from

$$\frac{68 \times 10}{22.7} \text{ g} = 29.9 \text{ g} \quad 30 \text{ g } \text{H}_2\text{O}_2$$

Therefore, strength of H_2O_2 in 10 volume H_2O_2 solution = 30 g/L = 3% H_2O_2 solution

Physical Properties of Hydrogen Peroxide

Melting point/K	272.4	Density (liquid at 298K)/g cm ⁻³	1.44
Boiling point (extrapolated)/K	423	Viscosity (290K)/centipoise	1.25
Vapour pressure (298 K) mmHg	1.9	Dielectric constant (298 K)/C ² /Nm ²	70.7
Density (Solid at 268.5 K)/g cm ⁻³	1.64	Electrical conductivity (298K)/Ω ⁻¹ cm ⁻¹	5.1 × 10 ⁻⁸

Structure

Hydrogen peroxide has a non-planar structure. The molecular dimensions in the gas phase and solid phase are shown in Fig.
























Fig. (a) H_2O_2 structure in gas phase, dihedral angle is 111.5°. (b) H_2O_2 structure in solid phase at 110K, dihedral angle is 90.2°.

Chemical Properties :



(ii) It is oxidant as well as reductant.

**Oxidising Properties:****Reducing properties:**







It acts as an oxidising as well as reducing agent in both acidic and alkaline media. Simple reactions are described below.



(i) Oxidising action in acidic medium



(ii) Reducing action in acidic medium



(iii) Oxidising action in basic medium



(iv) Reducing action in basic medium



◆ Storage

H_2O_2 decomposes slowly on exposure to light.



In the presence of metal surfaces or traces of alkali (present in glass containers), the above reaction is catalysed. It is, therefore, stored in wax-lined glass or plastic vessels in dark. Acetaldehyde or Glycerol or Urea can be added as a stabiliser. It is kept away from dust because dust can induce explosive decomposition of the compound.


Uses

Its wide scale use has led to tremendous increase in the industrial production of H_2O_2 .


Some of the uses are listed below :

- (i) In daily life it is used as a hair bleach and as a mild disinfectant. As an antiseptic it is sold in the market as perhydrol.
- (ii) It is used to manufacture chemicals like sodium perborate and per-carbonate, which are used in high quality detergents.
- (iii) It is used in the synthesis of hydroquinone, tartaric acid and certain food products and pharmaceuticals (cephalosporin) etc.
- (iv) It is employed in the industries as a bleaching agent for textiles, paper pulp, leather, oils, fats, etc.

- (v) As a rocket propellant:



- (vi) In detection of Cr^{+3} , Ti^{+4} etc.




Yellow or orange

Pertitanic acid

- (vii) Nowadays it is also used in Environmental (Green) Chemistry. For example, in pollution control treatment of domestic and industrial effluents, oxidation of cyanides, restoration of aerobic conditions to sewage wastes, etc.

ALLOTROPIC FORMS OF SULPHUR

Sulphur forms numerous allotropes of which the yellow rhombic (α -sulphur) and monoclinic (β -sulphur) forms are the most important. The stable form at room temperature is rhombic sulphur, which transforms to monoclinic sulphur when heated above 369 K.



At 369 K both the forms are stable. This temperature is called transition temperature.

Note: Viscosity of 'S' with temperature :


m.p. of 'S' $\longrightarrow$ 112.8°C .

$> 112.8^\circ\text{C}$ to $160^\circ\text{C} \Rightarrow$ slow decreases due to

S_8 rings slip and roll over one another easily.

$> 160^\circ\text{C}$, increases sharply due to breaking of

S_8 rings into chains and polymerises into large size chain.

**Amorphous forms are**

(i) Plastic sulphur


(ii) Milk of sulphur

(iii) Colloidal sulphur








SULPHUR DIOXIDE

Preparation


Sulphur dioxide is formed together with a little (6-8%) sulphur trioxide when sulphur is burnt in air or oxygen:



laboratory method by treating a sulphite with dilute sulphuric acid.

**Other preparation :**

Industrial method, by-product of the roasting of sulphide ores.




The gas after drying is liquefied under pressure and stored in steel cylinders.

Properties



- (i) Sulphur dioxide is a colourless gas with pungent smell.
- (ii) It is highly soluble in water.
- (iii) It liquefies at room temperature under a pressure of two atmospheres and boils at 263 K.
- (iv) **Acidic character** : sulphur dioxide, when passed through water, forms a solution of sulphurous acid.



It reacts readily with sodium hydroxide solution, forming sodium sulphite, which then reacts with more sulphur dioxide to form sodium hydrogen sulphite.





In its reaction with water and alkalis, the behaviour of sulphur dioxide is very similar to that of carbon dioxide. Sulphur dioxide reacts with chlorine in the presence of charcoal (which acts as a catalyst) to give sulphuryl chloride, SO_2Cl_2 . It is oxidised to sulphur trioxide by oxygen in the presence of vanadium(V) oxide catalyst.




Reducing properties

When moist, sulphur dioxide behaves as a reducing agent. For example, it converts iron(III) ions to iron(II) ions and decolourises acidified potassium permanganate(VII) solution; the latter reaction is a convenient test for the gas.



Bonding in SO_2 : The molecule of SO_2 is angular. It is a resonance hybrid of the two canonical forms:




Uses:

- (i) It is used refining petroleum and sugar
- (ii) It is used in bleaching wool and silk
- (iii) It is used as an anti-chlor, disinfectant and preservative. Sulphuric acid, sodium hydrogen sulphite and calcium hydrogen sulphite (industrial chemicals) are manufactured from sulphur dioxide. Liquid SO_2 is used as a solvent to dissolve a number of organic and inorganic chemicals.


HYDROGEN SULPHIDE (H_2S) SULPHURATED HYDROGEN

Preparation

By the action of dil. HCl or H_2SO_4 on iron pyrites.




Note: **Drying agent for this gas** : fused CaCl_2 , Al_2O_3 (dehydrated) P_2O_5 etc. But not H_2SO_4 ,




Properties

It is a colourless gas having an offensive smell of rotten eggs.

- (a) It burn in air with blue flame




If the air supply is in excess



- (b) It is a mild acid.




- (c) It act as a reducing agent. It reduces halogen into corresponding hydroacid.

**Tests of H_2S**

- (a) Unpleasant odour resembling that of rotten eggs.

- (b) It turns lead acetate into paper black



- (c) It gives a violet colouration with a alkaline solution of sodium nitroprusside.

Structure of H_2S


- (a) Similar to structure of water molecule i.e. V-shaped structure with bond length (H-S) $1.35\text{\AA}$ and bond angle (H-S-H) is 92.5°

Uses

- (a) It is mainly employed in salt analysis for the detection of cation.
 (b) Reducing agent for H_2SO_4 , KMnO_4 , $\text{K}_2\text{Cr}_2\text{O}_7$, O_3 , H_2O_2 , FeCl_3

OXOACIDS OF SULPHUR

Sulphur forms a number of oxoacids such as H_2SO_3 , $\text{H}_2\text{S}_2\text{O}_3$, $\text{H}_2\text{S}_2\text{O}_4$, $\text{H}_2\text{S}_2\text{O}_5$, $\text{H}_2\text{S}_x\text{O}_6$ ($x = 2$ to 5), H_2SO_4 , $\text{H}_2\text{S}_2\text{O}_7$, H_2SO_5 , $\text{H}_2\text{S}_2\text{O}_8$. Some of these acids are unstable and cannot be isolated. They are known in aqueous solution or in the form of their salts. Structures of some important oxoacids are shown in Fig.



Structures of some important oxoacids of sulphur

SULPHURIC ACID

Sulphuric acid is one of the most important industrial chemicals worldwide.

Industrial Manufacturing (Contact process)

Steps involved :

(i) **Burning of sulphur or sulphide ores in air to generate SO_2 .**

(ii) **Conversion of SO_2 to SO_3 by the reaction with oxygen in the presence of a catalyst (V_2O_5):**

The SO_2 produced is purified by removing dust and other impurities such as arsenic compounds.

The key step in the manufacture of H_2SO_4 is the catalytic oxidation of SO_2 with O_2 to give SO_3 in the presence of V_2O_5 (catalyst).





The reaction is exothermic, reversible and the forward reaction leads to a decrease in volume.

Therefore, low temperature and high pressure are the favourable conditions for maximum yield.

But the temperature should not be very low otherwise rate of reaction will become slow. In practice, the plant is operated at a pressure of 2 bar and a temperature of 720 K.

(iii) **Absorption of SO_3 in H_2SO_4 to give Oleum ($\text{H}_2\text{S}_2\text{O}_7$) :**

The SO_3 gas from the catalytic converter is absorbed in concentrated H_2SO_4 to produce oleum. Dilution of oleum with water gives H_2SO_4 of the desired concentration. In the industry two steps are carried out simultaneously to make the process a continuous one and also to reduce the cost.



Flow diagram for the manufacture of sulphuric acid

The sulphuric acid obtained by Contact process is 96-98% pure.

P_2O_5 is stronger dehydrating agent than H_2SO_4 : $\text{H}_2\text{SO}_4 + \text{P}_2\text{O}_5 \longrightarrow 2\text{HPO}_3 + \text{SO}_3$

Properties


- (i) Sulphuric acid is a colourless, dense, oily liquid with a specific gravity of 1.84 at 298 K.
- (ii) The acid freezes at 283 K and boils at 611 K.
- (iii) It dissolves in water with the evolution of a large quantity of heat. Hence, care must be taken while preparing sulphuric acid solution from concentrated sulphuric acid. The concentrated acid must be added slowly into water with constant stirring.

Chemical properties

The chemical reactions of sulphuric acid are as a result of the following characteristics:


- (a) low volatility
- (b) strong acidic character
- (c) strong affinity for water and
- (d) ability to act as an oxidising agent.
- (iv) **Acidic character :**

In aqueous solution, sulphuric acid ionises in two steps.



The larger value of K_{a_1} ($K_{a_1} > 10$) means that H_2SO_4 is largely dissociated into H^+ and HSO_4^- . Greater the value of dissociation constant (K_a), the stronger is the acid.





The acid forms two series of salts: normal sulphates (such as sodium sulphate and copper sulphate) and acid sulphates (e.g., sodium hydrogen sulphate). Sulphuric acid, because of its low volatility can be used to manufacture more volatile acids from their corresponding salts.



(M = Metal)








Dehydrating Property :

Concentrated sulphuric acid is a strong dehydrating agent. Many wet gases can be dried by passing them through sulphuric acid, provided the gases do not react with the acid. Sulphuric acid removes water from organic compounds; it is evident by its charring action on carbohydrates.













Oxidizing Nature :

Hot concentrated sulphuric acid is a moderately strong oxidising agent. In this respect, it is intermediate between phosphoric and nitric acids. Both metals and non-metals are oxidised by concentrated sulphuric acid, which is reduced to SO_2 .








 **H_2SO_4 & SO_3 :**

Uses: Sulphuric acid is a very important industrial chemical. A nation's industrial strength can be judged by the quantity of sulphuric acid it produces and consumes. It is needed for the manufacture of hundreds of other compounds and also in many industrial processes. The bulk of sulphuric acid produced is used in the manufacture of fertilisers (e.g., ammonium sulphate, superphosphate). Other uses are in:

- (i) petroleum refining
- (ii) manufacture of pigments, paints and dyestuff intermediates
- (iii) detergent industry
- (iv) metallurgical applications (e.g., cleansing metals before enameling, electroplating and galvanising)
- (v) storage batteries
- (vi) in the manufacture of nitrocellulose products and
- (vii) as a laboratory reagent.

SODIUM THIOSULPHATE**Preparation:**

[Na₂S is readily oxidised in air giving rise to Na₂S₂O₃]



HALOGEN FAMILY

GROUP 17 ELEMENTS (F, Cl, Br, I, At)

These are collectively known as the halogens (Greek halo means salt and genes means born i.e., salt producers). Astatine is a radioactive element.

❑ Occurrence

- (i) Fluorine and chlorine are fairly abundant while bromine and iodine less so.
- (ii) Fluorine is present mainly as insoluble fluorides (fluorspar CaF_2 , cryolite Na_3AlF_6 and fluoroapatite $3\text{Ca}_3(\text{PO}_4)_2 \cdot \text{CaF}_2$) and small quantities are present in soil, river water plants and bones and teeth of animals.
- (iii) Sea water contains chlorides, bromides and iodides of sodium, potassium, magnesium and calcium, but is mainly sodium chloride solution (2.5% by mass).
- (iv) The deposits of dried up seas contain these compounds, e.g., sodium chloride and carnallite, $\text{KCl} \cdot \text{MgCl}_2 \cdot 6\text{H}_2\text{O}$. Certain forms of marine life contain iodine in their systems; various seaweeds, for example, contain upto 0.5% of iodine and Chile saltpetre contains upto 0.2% of sodium iodate.

Electronic Configuration

The electronic configuration of outermost shell 17th group element is (ns^2np^5) .

❑ **Atomic and ionic radii :** $\text{F} < \text{Cl} < \text{Br} < \text{I}$

❑ **Ionisation Enthalpy :** $\text{F} > \text{Cl} > \text{Br} > \text{I}$

❑ **Most Negative Electron Gain Enthalpy:** $\text{Cl} > \text{F} > \text{Br} > \text{I}$

It is due to small size of fluorine atom. As a result, there are strong interelectronic repulsions in the relatively small 2p orbitals of fluorine and thus, the incoming electron does not experience much attraction.

❑ **Electronegativity :** $\text{F} > \text{Cl} > \text{Br} > \text{I}$

❑ Physical Properties

- (i) Their melting and boiling points steadily increase with atomic number.
- (ii) All halogens are coloured. For example, F_2 is a yellow gas, Cl_2 greenish yellow gas, Br_2 red liquid and I_2 violet coloured solid. Reason : Decrease in HOMO-LUMO gap.
- (iii) Fluorine and chlorine react with water. Bromine and iodine are only sparingly soluble in water but are soluble in various organic solvents such as chloroform, carbon tetrachloride, carbon disulphide and hydrocarbons to give coloured solutions.
- (iv) **Bond energy order ;** $\text{Cl}_2 > \text{Br}_2 > \text{F}_2 > \text{I}_2$

A reason for this anomaly is the relatively large electron-electron repulsion among the lone pairs in F_2 molecule where they are much closer to each other than in case of Cl_2 .

❑ Chemical Properties

Oxidation states :




- (i) All the halogens exhibit -1 oxidation state. However, chlorine, bromine and iodine exhibit $+1$, $+3$, $+5$ and $+7$ oxidation states also as explained below :

Halogen atom in ground state (other than fluorine)	ns $\uparrow\downarrow$	np $\uparrow\downarrow \uparrow\downarrow \uparrow$	nd $\square \square \square \square$	1 unpaired electron accounts for -1 or $+1$ oxidation states
First excited state	$\uparrow\downarrow$	$\uparrow\downarrow \uparrow \uparrow$	$\uparrow \square \square \square$	3 unpaired electron accounts for $+3$ oxidation states
Second excited state	$\uparrow\downarrow$	$\uparrow \uparrow \uparrow$	$\uparrow \uparrow \square \square$	5 unpaired electron accounts for $+5$ oxidation states
Third excited state	$\uparrow$	$\uparrow \uparrow \uparrow$	$\uparrow \uparrow \uparrow \square$	7 unpaired electron accounts for $+7$ oxidation states


- (ii) The higher oxidation states of chlorine, bromine and iodine are realised mainly when the halogens are in combination with the small and highly electronegative fluorine and oxygen atoms. e.g., in interhalogens, oxides and oxoacids.
- (iii) The oxidation states of $+4$ and $+6$ occur in the oxides and oxoacids of chlorine and bromine.
- (iv) The fluorine atom has no d orbitals in its valence shell and therefore cannot expand its octet. Being the most electronegative, it exhibits only -1 oxidation state.

Chemical reactivity

- (i) All the halogens are highly reactive.
- (ii) They react with metals and non-metals to form halides and the reactivity of the halogens decreases down the group. i.e. the order is $F_2 > Cl_2 > Br_2 > I_2$
- (iii) The ready acceptance of an electron is the reason for the strong oxidising nature of halogens. F_2 is the strongest oxidising halogen and it oxidises other halide ions in solution or even in the solid phase. In general, a halogen oxidises halide ions of higher atomic number.




The decreasing oxidising ability of the halogens in aqueous solution down the group is evident from their standard electrode potentials, which are dependent on the parameters as follows :




(1) Reactivity towards water

The relative oxidising power of halogens can further be illustrated by their reactions with water.

Fluorine oxidises water to oxygen whereas chlorine and bromine react with water to form corresponding hydrohalic and hypohalous acids. The reaction of iodine with water is nonspontaneous. In fact, I^- can be oxidised by oxygen in acidic medium; just the reverse of the reaction is observed with fluorine.



(where $X = Cl$ or Br)

**Note : Anomalous behaviour of fluorine**

- (i) Fluorine is anomalous in many properties. For example, ionisation enthalpy, electronegativity, and electrode potentials are all higher for fluorine than expected from the trends set by other halogens. Also, ionic and covalent radii, m.p. and b.p., enthalpy of bond dissociation and electron gain enthalpy are quite lower than expected.
- (ii) Most of the reactions of fluorine are exothermic (due to the small and strong bond formed by it with other elements).
- (iii) It forms only one oxoacid while other halogens form a number of oxoacids.
- (iv) Hydrogen fluoride is a liquid (b.p. 293 K) due to strong hydrogen bonding. Other hydrogen halides are gases.

Reason for the anomalous behaviour of fluorine

The anomalous behaviour of fluorine is due to its small size, highest electronegativity, low F-F bond dissociation enthalpy, and non availability of d orbitals in valence shell.

Properties of Hydrogen Halides


Property	HF	HCl	HBr	HI
Melting point/K	190	159	185	222
Boiling length (H – X)/pm	91.7	127.4	141.4	160.9
$\Delta_{\text{diss}}H^\circ/\text{kJ mol}^{-1}$	57.4	432	363	295
pK_a	3.2	-7.0	-9.5	-10.0

- (2) **Reactivity towards hydrogen** : They all react with hydrogen to give hydrogen halides but affinity for hydrogen decreases from fluorine to iodine. Hydrogen halides dissolve in water to form hydrohalic acids. Some of the properties of hydrogen halides are :

- (i) The acidic strength order : $HF < HCl < HBr < HI$
- (ii) The stability order of these halides : $H-F > H-Cl > H-Br > H-I$.






(3) Reactivity towards oxygen :

- (i) Halogens form many oxides with oxygen but most of them are unstable. Fluorine forms two oxides OF_2 and O_2F_2 . However, only OF_2 is thermally stable at 298 K. These oxides are essentially oxygen fluorides because of the higher electronegativity of fluorine than oxygen. Both are strong fluorinating agents. O_2F_2 oxidises plutonium to PuF_6 and the reaction is used in removing plutonium as PuF_6 from spent nuclear fuel.
 - (ii) Chlorine, bromine and iodine form oxides in which the oxidation states of these halogens range from +1 to +7.
 - (iii) A combination of kinetic and thermodynamic factors lead to the generally decreasing order of stability of oxides formed by halogens, $\text{I} > \text{Cl} > \text{Br}$.
 - (iv) The higher oxides of halogens tend to be more stable than the lower ones.
 - (v) Chlorine oxides, Cl_2O , ClO_2 , Cl_2O_6 and Cl_2O_7 are highly reactive oxidising agents and tend to explode. ClO_2 is used as a bleaching agent for paper pulp and textiles and in water treatment.
 - (vi) The bromine oxides, Br_2O , BrO_2 , BrO_3 are the least stable halogen oxides (middle row anomaly) and exist only at low temperatures. They are very powerful oxidising agents.
 - (vii) The iodine oxides, I_2O_4 , I_2O_5 , I_2O_7 are insoluble solids and decompose on heating. I_2O_5 is a very good oxidising agent and is used in the estimation of carbon monoxide.
- (4) Reactivity towards metals :** Halogens react with metals to form metal halides. For example, bromine reacts with magnesium to give magnesium bromide.



The ionic character of the halides decreases in the order $\text{MF} > \text{MCl} > \text{MBr} > \text{MI}$ where M is monovalent metal. If a metal exhibits more than one oxidation state, the halides in higher oxidation state will be more covalent than the one in lower oxidation state. For example, SnCl_4 , PbCl_4 , SbCl_5 and UF_6 are more covalent than SnCl_2 , PbCl_2 , SbCl_3 and UF_4 respectively.

- (5) Reactivity of halogens towards other halogens :** Halogens combine amongst themselves to form a number of compounds known as interhalogens of the types XX' , XX_3' , XX_5' and XX_7' where X is a larger size halogen and X' is smaller size halogen.



FLUORINE**Method of Preparation :****Moissan process :** [By electrolysis of KHF_2 (which is obtained from CaF_2)]**BROMINE****IODINE****CHLORINE**

Chlorine was discovered in 1774 by Scheele by the action of HCl on MnO_2 .

In 1810 Davy established its elementary nature and suggested the name chlorine on account of its colour (Greek, chloros = greenish yellow).

Preparation

(i) By electrolysis of aq. NaCl :



(ii) By heating manganese dioxide with concentrated hydrochloric acid.



However, a mixture of common salt and concentrated H_2SO_4 is used in place of HCl .




(iii) By the action of HCl on potassium permanganate.



□ Manufacture of chlorine




- (i) **Deacon's process** : By oxidation of hydrogen chloride gas by atmospheric oxygen in the presence of CuCl_2 (catalyst) at 723 K.



- (ii) **Electrolytic process** : Chlorine is obtained by the electrolysis of brine (concentrated NaCl solution). Chlorine is liberated at anode. It is also obtained as a by product in many chemical industries.




Properties

- It is a greenish yellow gas with pungent and suffocating odour.
- It is about 2-5 times heavier than air.
- It can be liquefied easily into greenish yellow liquid which boils at 239 K.
- It is soluble in water. Chlorine reacts with a number of metals and non-metals to form chlorides.




Reaction with hydrogen

It has great affinity for hydrogen. It reacts with compounds containing hydrogen to form HCl .




Reaction with ammonia

With excess ammonia, chlorine gives nitrogen and ammonium chloride whereas with excess chlorine, nitrogen trichloride (explosive) is formed.



(excess)



(excess)

Reaction with alkalis

With cold and dilute alkalis chlorine produces a mixture of chloride and hypochlorite but with hot and concentrated alkalis it gives chloride and chlorate.





(cold and dilute)



(hot and conc.)


but on acidification the disproportionated product gives back the same element.



[X = Cl, Br, I]

Reaction with slaked lime



With dry slaked lime it gives bleaching powder.



The composition of bleaching powder is $\text{Ca}(\text{OCl})_2 \cdot \text{CaCl}_2 \cdot \text{Ca}(\text{OH})_2 \cdot 2\text{H}_2\text{O}$.



Reaction with hydrocarbon

Chlorine reacts with hydrocarbons and gives substitution products with saturated hydrocarbons and addition products with unsaturated hydrocarbons. For example,


**Note :**

Chlorine water on standing loses its yellow colour due to the formation of HCl and HOCl. Hypochlorous acid (HOCl) so formed, gives nascent oxygen which is responsible for oxidising and bleaching properties of chlorine.

- (i) It oxidises ferrous to ferric and sulphite to sulphate. Chlorine oxidises sulphur dioxide to sulphur trioxide and iodine to iodate. In the presence of water they form sulphuric acid and iodic acid respectively.



- (ii) It is a powerful bleaching agent; bleaching action is due to oxidation.





Coloured substance + O → Colourless substance








Uses: It is used (i) for bleaching woodpulp (required for the manufacture of paper and rayon), bleaching cotton and textiles, (ii) in the extraction of gold and platinum (iii) in the manufacture of dyes, drugs and organic compounds such as CCl_4 , CHCl_3 , DDT, refrigerants, etc. (iv) in sterilising drinking water and (v) preparation of poisonous gases such as phosgene (COCl_2), tear gas (CCl_3NO_2), mustard gas ($\text{ClCH}_2\text{CH}_2\text{SCH}_2\text{CH}_2\text{Cl}$). (vi) It bleaches vegetable or organic matter in the presence of moisture. Bleaching effect of chlorine is permanent.




(a) On long standing it undergoes



Oxidising Properties:



Reaction with acid:



Note: ClO_2 does not dimerise because odd electron undergoes delocalisation (in its own vacant 3d-orbital)

Cl_2O_4 ($\text{Cl}.\text{ClO}_4$) is not the dimer of ClO_2 . Actually it is Cl-perchlorate.



HYDROGEN CHLORIDE

(i) Glauber prepared this acid in 1648 by heating common salt with concentrated sulphuric acid.

(ii) Davy in 1810 showed that it is a compound of hydrogen and chlorine.

Preparation

Laboratory method : it is prepared by heating sodium chloride with concentrated sulphuric acid.




HCl gas can be dried by passing through concentrated sulphuric acid.


Properties

- (i) It is a colourless and pungent smelling gas. Due to strong affinity for water, conc. HCl pulls moisture of air towards self. The moisture forms droplets of water and hence, cloudy white fumes appear.
- (ii) It is easily liquefied to a colourless liquid (b.p. 189 K) and freezes to a white crystalline solid (f.p. 159 K).

- (iii) It is extremely soluble in water
 (iv) **Acidic character** : It ionises as follows





Its aqueous solution is called hydrochloric acid. High value of dissociation constant (K_a) indicates that it is a strong acid in water. It reacts with NH_3 and gives white fumes of NH_4Cl .






Note : Aqua regia

When three parts of concentrated HCl and one part of concentrated HNO_3 are mixed, aqua regia is formed which is used for dissolving noble metals, e.g., gold, platinum.



Reaction with salts

Hydrochloric acid decomposes salts of weaker acids, e.g., carbonates, hydrogencarbonates, sulphites, etc.






Uses:

- It is used in the manufacture of chlorine, NH_4Cl and glucose (from corn starch)
- It is used for extracting glue from bones and purifying bone black
- It is used in medicine and as a laboratory reagent.


OXOACIDS OF HALOGENS

- Due to high electronegativity and small size, fluorine forms only one oxoacid, HOF known as fluoric (I) acid or hypofluorous acid.
- The other halogens form several oxoacids.
- Most of them cannot be isolated in pure state. They are stable only in aqueous solutions or in the form of their salts.

Oxiacids of Halogens				
Halic (I) acid (Hypophalous acid)	HOF Hypoflorous acid	HOCl (Hypochlorous acid)	HOBr (Hypobromous acid)	HOI (Hypoiodous acid)
Halic (III) acid (Halous acid)	=	HOClO (Chlorous acid)	=	=
Halic (V) acid (Halic acid)	=	HOClO₂ (Chloric acid)	HOBrO₂ (Bromic acid)	HOIO₂ (Iodic acid)
Halic (VII) acid (Perhalic acid)	=	HOClO₃ (Perchloric acid)	HOBrO₃ (Perbromic acid)	HOIO₃ (Periodic acid)




The structures of
oxoacids of
chlorine



INTERHALOGEN COMPOUNDS

When two different halogens react with each other, interhalogen compounds are formed. They can be assigned general compositions as XX' , XX_3' , XX_5' and XX_7' where X is halogen of larger size and X' of smaller size and X is more electropositive than X' . As the ratio between radii of X and X' increases, the number of atoms per molecule also increases. Thus, iodine (VII) fluoride should have maximum number of atoms as the ratio of radii between I and F should be maximum. That is why its formula is IF_7 (having maximum number of atoms).



There are never more than two halogens in a molecule.


Bonds are essentially covalent and b.p. increases as the E.N. difference increases.

AX_5 & AX_7 type formed by large atoms like Br & I to accommodate more atoms around it.

The interhalogens are generally more reactive than the halogens (except F_2) due to weaker A–X bonds compared to X–X bond.

Preparation

The interhalogen compounds can be prepared by the direct combination or by the action of halogen on lower interhalogen compounds. The product formed depends upon some specific conditions, For e.g.,



Properties


Some properties of interhalogen compounds are given in Table below

Some properties of Interhalogen Compounds

Type	Formula	Physical state and colour	Structure
XX'_1	ClF	Colourless gas	—
	BrF	pale brown gas	—
	IF ^a	Detected spectroscopically	—
	BrCl ^b	gas	—
	ICl	ruby red solid (α -form) brown red solid (β -form)	—
	IBr	black solid	—
XX'_3	ClF ₃	colourless gas	Bent T-shaped
	BrF ₃	yellow green liquid	Bent T-shaped
	IF ₃	yellow powder	Bent T-shaped
	ICl ₃ ^c	orange solid	Bent T-shaped
XX'_5	IF ₅	colourless gas but solid below 77 K	Square pyramidal
	BrF ₅	colourless liquid	Square pyramidal
	ClF ₅	colourless liquid	Square pyramidal
XX'_7	IF ₇	colourless gas	Pentagonal bipyramidal

^aVery unstable; ^bThe pure solid is known at room temperature; ^cDimerises as Cl-bridged dimer (I_2Cl_6)

One peculiarity with ICl :



- These are all covalent molecules and are diamagnetic in nature.
- They are volatile solids or liquids at 298 K except ClF which is a gas.
- Their physical properties are intermediate between those of constituent halogens except that their m.p. and b.p. are a little higher than expected.

PSEUDO HALOGENS

There are univalent ion consisting of two or more atoms of which at least one is N, that have properties similar to those of the halide ions. E.g.

- (i) Na-salts are soluble in water but Ag-salts are insoluble in water.
- (ii) H-compounds are acids like HX.
- (iii) Some anions can be oxidised to give molecules X_2 .


Anions :	Acids	Dimer
CN^-	HCN	$(CN)_2$
SCN^-	HSCN(thiocyanic acid)	$(SCN)_2$
$SeCN^-$		$(SeCN)_2$
OCN^-	HOCN (cyanic acid)	
NCN^{2-} (Bivalent)	H_2NCN (cyanamide)	
ONC^-	HONC (Fulminic acid)	
N_3^-	HN_3 (Hydrazoic acid)	

$CN^\ominus$ shows maximum similarities with Cl^- , Br^- , I^-

- (i) forms HCN (ii) forms $(CN)_2$ (iii) AgCN, $Pb(CN)_2$, are insoluble
- (iv) Interpseudo halogen compounds ClCN, BrCN, ICN can be formed
- (v) AgCN is insoluble in H_2O but soluble in NH_3
- (vi) forms large no. of complexes. e.g. $[Cu(CN)_4]^{3-}$ & $[CuCl_4]^{3-}$

NOBLE GASES FAMILY**GROUP 18 ELEMENTS (He, Ne, Ar, Kr, Xe, Rn)****Occurrence**

- (i) All the noble gases except radon occur in the atmosphere.
Relative abundance : Ar is highest (Ne, Kr, He, Rn)
- (ii) Their atmospheric abundance in dry air is ~ 1% by volume of which argon is the major constituent.
- (iii) Helium and sometimes neon are found in minerals of radioactive origin e.g., pitchblende, monazite, cleveite.
- (iv) The main commercial source of helium is natural gas.
- (v) Xenon and radon are the rarest elements of the group.
- (vi) Radon is obtained as a decay product of ^{226}Ra .



- (vii) He liquid can exist in two forms. I-form when changes to II-form at λ -point temperature many physical properties change abruptly.

e.g.

- (i) Sp. heat changes by a factor of 10
- (ii) Thermal conductivity increases by 10^6 and it becomes 800 times faster than Cu
- (iii) It shows zero resistance
- (iv) It can flow up the sides of the vessel

Qus. Why 18 group element are termed as noble gas ?

Ans. All these are gases and chemically unreactive. They form very few compounds. Because of this they are termed noble gases.


❑ **Electronic Configuration**

General electronic configuration of 18 group element is ns^2np^6 except helium which has $1s^2$.

Many of the properties of noble gases including their inactive nature are ascribed to their closed shell structures.

❑ **Ionisation Enthalpy**

Ionisation energy decreases down the group with increase in atomic size.



Due to stable electronic configuration these gases exhibit very high ionisation enthalpy.

❑ **Atomic Radii**

Atomic radii increase down the group with increase in atomic number.



❑ **Electron Gain Enthalpy**

They have large positive values of electron gain enthalpy due to stable electronic configurations, and therefore have no tendency to accept the electron

❑ **Melting point and boiling point**



↓

(-269°C)

B.P. order : $\text{He} < \text{Ne} < \text{Ar} < \text{Kr} < \text{Xe} < \text{Rn}$ (Boiling point order)

❑ **Density order :**



Physical properties :

(i) All the noble gases are monoatomic.

(ii) They are colourless, odourless and tasteless.

(iii) They are sparingly soluble in water.

(iv) They have very low melting and boiling points because the only type of interatomic interaction in these elements is weak dispersion forces.

(v) Helium has the lowest boiling point (4.2 K) of any known substance.

(vi) It has an unusual property of diffusing through most commonly used laboratory materials such as rubber, glass or plastics.

❑ Chemical Properties





In general, noble gases are least reactive. Their inertness to chemical reactivity is attributed to the following reasons:

- The noble gases except helium ($1s^2$) have completely filled ns^2np^6 electronic configuration in their valence shell.
- They have high ionisation enthalpy and more positive electron gain enthalpy.

Note : The reactivity of noble gases has been investigated occasionally. In March 1962, Neil Bartlett, then at the University of British Columbia, observed the reaction of a noble gas. First, he prepared a red compound which is formulated as $O_2^+ PtF_6^-$. He, then realised that the first ionisation enthalpy of molecular oxygen (1175 kJ mol^{-1}) was almost identical with that of xenon (1170 kJ mol^{-1}). He made efforts to prepare same type of compound with Xe and was successful in preparing another red colour compound $Xe^+PtF_6^-$ by mixing PtF_6 and xenon. After this discovery, a number of xenon compounds mainly with most electronegative elements like fluorine and oxygen, have been synthesised. The compounds of krypton are fewer. Only the difluoride (KrF_2) has been studied in detail. Compounds of radon have not been isolated but only identified (e.g., RnF_2) by radiotracer technique. No true compounds of Ar, Ne or He are yet known.

FLUORIDES OF XENON

Preparation




Physical properties



XeF_2 , XeF_4 and XeF_6 are colourless crystalline solids and sublime readily at 298 K.

Chemical properties



- (i) **Hydrolysis :** They are readily hydrolysed even by traces of water. For example, XeF_2 is hydrolysed to give Xe, HF and O_2 .




Hydrolysis of XeF_4 and XeF_6 with water gives XeO_3 .






Partial hydrolysis of XeF_6 gives oxyfluorides, $XeOF_4$ and XeO_2F_2 .





Note : Hydrolysis in alkaline medium


(ii) **As fluorinating agents :** They are powerful fluorinating agents.



(iii) **As fluoride donor**




(iv) **As Fluoride acceptor**



(alkali metals fluoride)

(v) **Reaction with SiO₂**

SiO₂ also converts XeF₆ into XeOF₄





Similarly, $\text{XeO}_3 + \text{XeOF}_4 \longrightarrow 2\text{XeO}_2\text{F}_2$

(vi) **Oxidizing properties**

H₂ reduces Xe – fluorides to Xe



Xe - fluorides oxidise Cl⁻ to Cl₂ and I⁻ to I₂




Noble gas hydrate (clathrate compound) : Ar, Kr, Xe can form clathrate compounds but He, Ne cannot due to their smaller size.


eg. $\text{Xe} \cdot 6\text{H}_2\text{O}$	} formed only when water freezes at high pressure together with noble gas
$\text{Ar} \cdot 6\text{H}_2\text{O}$	
$\text{Kr} \cdot 6\text{H}_2\text{O}$	

(a) Structure and bonding


XeF_2 and XeF_4 have linear and square planar structures respectively. XeF_6 has seven electron pairs (6 bonding pairs and one lone pair) and would, thus, have a distorted octahedral structure as found experimentally in the gas phase. Xenon fluorides react with fluoride ion acceptors to form cationic species and fluoride ion donors to form fluoroanions.



(a) Linear




(b) Square planar



(c) Distorted octahedral


(b) Xenon-oxygen compounds

XeO_3 is a colourless, white hygroscopic explosive solid and has a pyramidal molecular structure.



Pyramidal

XeOF_4 is a colourless volatile liquid and has a square pyramidal molecular structure.



Square pyramidal

Uses of helium :

- (i) He is a non-inflammable and light gas. Hence, it is used in filling balloons for meteorological observations.
- (ii) It is also used in gas-cooled nuclear reactors.
- (iii) It is used in cryoscopy to obtain the very low temperature required for superconductor and laser (b.p. 4.2 K) finds use as cryogenic agent for carrying out various experiments at low temperatures.
- (iv) It is used to produce and sustain powerful superconducting magnets which form an essential part of modern NMR spectrometers and Magnetic Resonance Imaging (MRI) systems for clinical diagnosis.
- (v) It is used as a diluent for oxygen in modern diving apparatus because of its very low solubility in blood. He is used in preference to N_2 to dil. O_2 in the gas cylinders used by divers. This is because N_2 is quite soluble in blood, so a sudden change in pressure causes degassing and gives bubbles of N_2 in the blood. This causes the painful condition called bends. He is slightly soluble so the risk of bends is reduced.

USES OF NEON :

- (i) Ne is used in discharge tubes and fluorescent bulbs for advertisement display purposes.
- (ii) Neon bulbs are used in botanical gardens and in green houses.

USES OF ARGON :

- (i) Argon is used mainly to provide an inert atmosphere in high temperature metallurgical processes (arc welding of metals or alloys) and for filling electric bulbs.
- (ii) It is also used in the laboratory for handling substances that are air-sensitive.

USES OF XENON AND KRYPTON :

There are no significant uses of Xenon and Krypton. They are used in light bulbs designed for special purposes.

SOLVED EXAMPLE

1. Though nitrogen exhibits +5 oxidation state, it does not form pentahalide. Give reason.


Sol. Nitrogen with $n = 2$, has s and p orbitals only. It does not have d orbitals to expand its covalency beyond four. That is why it does not form pentahalide.

2. PH_3 has lower boiling point than NH_3 . Why?

Sol. Unlike NH_3 , PH_3 molecules are not associated through hydrogen bonding in liquid state. That is why the boiling point of PH_3 is lower than NH_3 .

3. Write the reaction of thermal decomposition of sodium azide.

Sol. Thermal decomposition of sodium azide gives dinitrogen gas.





4. Why does NH_3 act as a Lewis base ?

Sol. Nitrogen atom in NH_3 has one lone pair of electrons which is available for donation. Therefore, it acts as a Lewis base.


5. NH_3 can't be dried by H_2SO_4 , P_2O_5 and anhydrous CaCl_2

Sol. because : $2\text{NH}_3 + \text{H}_2\text{SO}_4 \longrightarrow (\text{NH}_4)_2\text{SO}_4$



forms adduct

Quick lime is used for this purpose



6. Why does NO_2 dimerise ?

Sol. NO_2 contains odd number of valence electrons. It behaves as a typical odd molecule. On dimerisation, it is converted to stable N_2O_4 molecule with even number of electrons.

7. In what way can it be proved that PH_3 is basic in nature?


Sol. PH_3 reacts with acids like HI to form PH_4I which shows that it is basic in nature.



Due to lone pair on phosphorus atom, PH_3 is acting as a Lewis base in the above reaction.

8. Why does PCl_3 fume in moisture ?

Sol. PCl_3 hydrolyses in the presence of moisture giving fumes of HCl.



9. Are all the five bonds in PCl_5 molecule equivalent? Justify your answer.

Sol. PCl_5 has a trigonal bipyramidal structure and the three equatorial P-Cl bonds are equivalent, while the two axial bonds are different and longer than equatorial bonds.

10. How do you account for the reducing behaviour of H_3PO_2 on the basis of its structure?

Sol. In H_3PO_2 , two H atoms are bonded directly to P atom which imparts reducing character to the acid.

11. Elements of Group 16 generally show lower value of first ionisation enthalpy compared to the corresponding periods of group 15. Why?

Sol. Due to extra stable half-filled p orbitals electronic configurations of Group 15 elements, larger amount of energy is required to remove electrons compared to Group 16 elements.

12. H_2S is less acidic than H_2Te . Why?

Sol. Due to the decrease in bond (E-H) dissociation enthalpy down the group, acidic character increases.

13. Which form of sulphur shows paramagnetic behaviour?

Sol. In vapour state sulphur partly exists as S_2 molecule which has two unpaired electrons in the antibonding π^* orbitals like O_2 and, hence, exhibits paramagnetism.

14. What happens when

(i) Concentrated H_2SO_4 is added to calcium fluoride

(ii) SO_3 is passed through water?

Sol. (i) It forms hydrogen fluoride



(ii) It dissolves SO_3 to give H_2SO_4 .



15. Halogens have maximum negative electron gain enthalpy in the respective periods of the periodic table. Why?

Sol. Halogens have the smallest size in their respective periods and therefore high effective nuclear charge. As a consequence, they readily accept one electron to acquire noble gas electronic configuration.

16. Although electron gain enthalpy of fluorine is less negative as compared to chlorine, fluorine is a stronger oxidising agent than chlorine. Why?

Sol. It is due to


(i) low enthalpy of dissociation of F-F bond

(ii) high hydration enthalpy of F^-

17. Fluorine exhibits only -1 oxidation state whereas other halogens exhibit $+1$, $+3$, $+5$ and $+7$ oxidation states also. Explain.


Sol. Fluorine is the most electronegative element and cannot exhibit any positive oxidation state. Other halogens have d orbitals and therefore, can expand their octets and show $+1$, $+3$, $+5$ and $+7$ oxidation states also.

18. Write the balanced chemical equation for the reaction of Cl_2 with hot and concentrated NaOH . Is this reaction a disproportionation reaction? Justify.





Yes, chlorine from zero oxidation state is changed to -1 and $+5$ oxidation states.

19. CaF_2 used in HF prepⁿ. must be free from SiO_2 . Explain.



If SiO_2 present as impurity




Hence presence of one molecule SiO_2 consumes 6 molecule of HF

HF can not be stored in glass vessel due to same reason.

20. When HCl reacts with finely powdered iron, it forms ferrous chloride and not ferric chloride. Why?


Sol. Its reaction with iron produces H_2 .



Liberation of hydrogen prevents the formation of ferric chloride.

21. Discuss the molecular shape of BrF_3 on the basis of VSEPR theory.

Sol. The central atom Br has seven electrons in the valence shell. Three of these will form electronpair bonds with three fluorine atoms leaving behind four electrons. Thus, there are three bond pairs and two lone pairs. According to VSEPR theory, these will occupy the corners of a trigonal bipyramid. The two lone pairs will occupy the equatorial positions to minimise lone pair-lone pair and the bond pair-lone pair repulsions which are greater than the bond pair-bond pair repulsions. In addition, the axial fluorine atoms will be bent towards the equatorial fluorine in order to minimise the lone-pair-lone pair repulsions. The shape would be that of a slightly bent 'T'.



22. Why are the elements of Group 18 known as noble gases ?

Sol. The elements present in Group 18 have their valence shell orbitals completely filled and, therefore, react with a few elements only under certain conditions. Therefore, they are now known as noble gases.

23. Noble gases have very low boiling points. Why?

Sol. Noble gases being monoatomic have no interatomic forces except weak dispersion forces and therefore, they are liquefied at very low temperatures. Hence, they have low boiling points.

24. Does the hydrolysis of XeF_6 lead to a redox reaction?

Sol. No, the products of hydrolysis are XeOF_4 and XeO_2F_2 where the oxidation states of all the elements remain the same as it was in the reacting state.

25. Standard electrode potential values, $E^\ominus$ for Al^{3+}/Al is -1.66 V and that of Tl^{3+}/Tl is $+1.26 \text{ V}$. Predict about the formation of M^{3+} ion in solution and compare the electropositive character of the two metals.

Sol. Standard electrode potential values for two half cell reactions suggest that aluminium has high tendency to make $\text{Al}^{3+}(\text{aq})$ ions, whereas Tl^{3+} is not only unstable in solution but is a powerful oxidising agent also. Thus Tl^+ is more stable in solution than Tl^{3+} . Aluminium being able to form +3 ions easily, is more electropositive than thallium.

26. White fumes appear around the bottle of anhydrous aluminium chloride. Give reason.

Sol. Anhydrous aluminium chloride is partially hydrolysed with atmospheric moisture to liberate HCl gas. Moist HCl appears white in colour.

27. Boron is unable to form BF_6^{3-} ion. Explain.

Sol. Due to non-availability of d orbitals, boron is unable to expand its octet. Therefore, the maximum covalence of boron cannot exceed 4.

28. Why is boric acid considered as a weak acid ?

Sol. Because it is not able to release H^+ ions on its own. It receives OH^- ions from water molecule to complete its octet and in turn releases H^+ ions.

29. Select the member(s) of group 14 that (i) forms the most acidic dioxide, (ii) is commonly found in +2 oxidation state, (iii) used as semiconductor.

Sol. (i) carbon (ii) lead (iii) silicon and germanium

30. $[\text{SiF}_6]^{2-}$ is known whereas $[\text{SiCl}_6]^{2-}$ not. Give possible reasons.

Sol. The main reasons are :

(i) six large chloride ions cannot be accommodated around Si^{4+} due to limitation of its size.

(ii) interaction between lone pair of chloride ion and Si^{4+} is not very strong.

31. Diamond is covalent, yet it has high melting point. Why ?

Sol. Diamond has a three-dimensional network involving strong C—C bonds, which are very difficult to break and, in turn has high melting point.

32. SiH_4 is more reactive than CH_4 . Explain

Reasons

(i) $\text{Si}^{\delta+} - \text{H}^{\delta-}$ in $\text{C}^{\delta-} - \text{H}^{\delta+}$

C - more electronegative than H

Si less electronegative than H

So bond polarity is reversed when Nu^- attacks, it faces repulsion in C but not in Si

(ii) Silicon is having vacant d orbital which is not in case of carbon

(iii) Silicon is larger in size compared to C. By which the incoming Nu^- doesn't face any steric hindrance to attack at Si whereas CH_4 is tightly held from all sides.